

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Lake Fork Ranch 4-13B4				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT ALTAMONT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR EP ENERGY E&P COMPANY, L.P.						7. OPERATOR PHONE 713 997-5038				
8. ADDRESS OF OPERATOR 1001 Louisiana, Houston, TX, 77002						9. OPERATOR E-MAIL maria.gomez@epenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Ute 1420H621743			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Lake Fork Ranch						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-454-3546				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') HC 65 Box 510048, Mountain Home, UT 84051						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') Ute			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		2569 FNL 2526 FWL		SEnw	13	2.0 S	4.0 W	U		
Top of Uppermost Producing Zone		2569 FNL 2526 FWL		SEnw	13	2.0 S	4.0 W	U		
At Total Depth		2569 FNL 2526 FWL		SEnw	13	2.0 S	4.0 W	U		
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 2526			23. NUMBER OF ACRES IN DRILLING UNIT 640				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1100			26. PROPOSED DEPTH MD: 13325 TVD: 13325				
27. ELEVATION - GROUND LEVEL 6059			28. BOND NUMBER RLB0009692			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Duchesne City				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
COND	17.5	13.375	0 - 600	54.5	J-55 ST&C	8.8	Class G	758	1.15	15.8
SURF	12.25	9.625	0 - 3300	40.0	N-80 LT&C	9.6	Unknown	450	3.16	11.0
							Unknown	191	1.33	14.3
I1	8.75	7	0 - 10600	29.0	HCP-110 LT&C	11.5	Unknown	485	2.31	12.0
							Unknown	91	1.91	12.5
L1	6.125	4.5	10400 - 13325	13.2	HCP-110 LT&C	13.3	Unknown	236	1.47	14.2
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Maria S. Gomez				TITLE Principal Regulatory Analyst			PHONE 713 997-5038			
SIGNATURE				DATE 12/05/2013			EMAIL maria.gomez@epenergy.com			
API NUMBER ASSIGNED 43013527190000				APPROVAL Permit Manager						

**Lake Fork Ranch 4-13B4
Sec. 13, T2S, R4W
DUCHESNE COUNTY, UT**

EP ENERGY E&P COMPANY, L.P.

DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers

<u>Formation</u>	<u>Depth</u>
Green River (GRRV)	5,408' TVD
Green River (GRTN1)	6,372' TVD
Mahogany Bench	7,386' TVD
L. Green River	8,721' TVD
Wasatch	10,550' TVD
T.D. (Permit)	13,325' TVD

2. Estimated Depths of Anticipated Water, Oil, Gas or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River (GRRV)	5,408' MD / TVD
	Green River (GRTN1)	6,372' MD / TVD
	Mahogany Bench	7,386' MD / TVD
Oil	L. Green River	8,721' MD / TVD
Oil	Wasatch	10,550' MD / TVD

3. Pressure Control Equipment: (Schematic Attached)

A 5.0" by 20.0" rotating head on structural pipe from surface to 600' MD/TVD. A 5.0" by 13-3/8" Smith Rotating Head (Diverter Stack) from 600' MD/TVD to 3,300' MD/TVD on Conductor. A 10M BOP stack w/ rotating head, 10M annular, blind rams & mud cross from 3,300' MD/TVD to 10,600' MD/TVD. A 10M BOP stack w/ rotating head, 10M annular, blind rams & mud cross from 10,600' MD/TVD to TD (13,325' MD/TVD).

The BOPE and related equipment will meet the requirements of the 5M and 10M system.

OPERATORS MINIMUM SPECIFICATIONS FOR BOPE:

The surface casing will be equipped with a flanged casing head of 5M psi working pressure. An 11" 5M x 11" 10M spool, 11" x 10M psi BOP and 5M psi annular will be nipped up on the surface casing and tested to 250 psi low test / 3,000 psi high test for 10 minutes each prior to drilling out. The surface casing will be tested to 1,000 psi. for 30 mins. Intermediate casing will be tested to the

greater of 1,500 psi or 0.22 psi/ft. The choke manifold equipment, upper Kelly cock and floor safety valves will be tested to 5M psi. The annular preventer will be tested to 250 psi low test / 4,000 psi high test. The 10M BOP will be installed with rotating head, spacer spool, 10M annular, 3-½ x 5" flex rams, blind rams, mud cross, single w/ flex rams, and B section from surface shoe to TD. The BOPE will be hydraulically operated.

In addition, the BOP equipment will be tested after running intermediate casing, after any repairs to the equipment and at least once every 30 days. Pipe and blind rams will be activated on each trip, annular preventer will be activated weekly and weekly BOP drills will be held with each crew.

Statement on Accumulator System and Location of Hydraulic Controls:

Patterson Rig # 307 is expected to be used to drill the proposed well. Operations will commence after approval of this application. Manual and/or hydraulic controls will be in compliance with 5M and 10M psi systems.

Auxiliary Equipment:

- A) Pason Gas Monitoring 600' - TD
- B) Mud logger with gas monitor – 3,300' to TD (13,325' MD/TVD)
- C) Choke manifold with one manual and one hydraulic operated choke
- D) Full opening floor valve with drill pipe thread
- E) Upper and lower Kelly cock
- F) Shaker, de-sander and centrifuge

4. Proposed Casing & Cementing Program:

Please refer to the attached Wellbore Diagram.

All casing will meet or exceed the following design safety factors:

- Burst = 1.00
- Collapse = 1.125
- Tension = 1.2 (including 100k# overpull)

Cement design calculations for intermediate and production hole will be based on minimum 10% excess over gauge hole volumes. Actual volumes pumped will be a minimum of 10% excess over caliper volume to designed tops of cement for any section logged. A minimum of 50% excess over gauge volume will be pumped on surface casing.

5. Drilling Fluids Program:

Proposed Mud Program:

Interval	Type	Mud Weight
Surface	WBM	8.8 – 9.6
Intermediate	WBM	9.6 – 11.5
Production	WBM	11.5 – 13.3

Anticipated mud weights are based on actual offset well bottom-hole pressure data. Mud weights utilized may be somewhat higher to allow for trip margin and to provide hole stability for running logs and casing.

Visual mud monitoring equipment will be utilized.

6. **Evaluation Program:**

Logs:

Mud Log: 3,300' MD/TVD – TD (13,325' MD/TVD)

Open Hole Logs: Gamma Ray, Neutron-Density, Resistivity, Sonic, from surface casing shoe to TD.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 13,325' TVD equals approximately 9,216 psi. This is calculated based on a 0.6916 psi/ft gradient (13.3 ppg mud density at TD).

Maximum anticipated surface pressure equals approximately 6,284 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/ft).

Maximum anticipated surface pressure based on frac gradient at 7" casing shoe is 0.8 psi/ft at 10,600' TVD = 8,480 psi


BOPE and casing design will be based on the lesser of the two MASPs which is 6,284 psi.

8. **OPERATOR REQUESTS THAT THE PROPOSED WELL BE PLACED ON CONFIDENTIAL STATUS.**



Drilling Schematic

Company Name: EP ENERGY	Date: November 19, 2013
Well Name: Lake Fork Ranch 4-13B4	TD: 13,325
Field, County, State: Altamont, Duchesne, Utah	AFE #: TBD
Surface Location: Sec 13 T2S R4W 2569' FNL 2526' FWL	BHL: Straight Hole
Objective Zone(s): Green River, Wasatch	Elevation: 6058.7
Rig: Patterson 307	Spud (est.): TBD
BOPE Info: Diverter from 600' to 3,300' 11 10M BOP stack w/rotating head, 10M annular, rams, blind rams & mud cross used from 3,300' to 10,600' 11 10M BOE w/rotating head, 10M annular, pipe rams, blind rams & mud cross from 10,600' to TD	



DRILLING PROGRAM

CASING PROGRAM	SIZE	INTERVAL		WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	13 3/8"	0	600	54.5	J-55	STC	2,740	1,130	514
SURFACE	9-5/8"	0	3300	40.00	N-80	LTC	5,750	3,090	737
INTERMEDIATE	7"	0	10600	29.00	HCP-110	LTC	11,220	9,750	797
PRODUCTION LINER	4-1/2"	10400	13325	13.50	HCP-110	LTC	12,420	11,810	338

CEMENT PROGRAM		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
CONDUCTOR		600	Class G + 3% CACL2	758	100%	15.8 ppg	1.15
SURFACE	Lead	2,800	EXTENDACEM (TM) SYSTEM: 5 lbm/sk Silicalite Compacted + 0.25 lbm/sk Kwik Seal + 0.125 lbm/sk Poly-E-Flake + 2% Bentonite	450	75%	11.0 ppg	3.16
	Tail	500	HALCEM (TM) SYSTEM: 3 lbm/sk Silicalite Compacted + 1% Salt + 0.3% Econolite + 0.25 lbm/sk Poly-E-Flake + 0.25 lbm/sk Kwik Seal + 0.5% HR-5	191	50%	14.3 ppg	1.33
INTERMEDIATE	Lead	6,800	EXTENDACEM (TM) SYSTEM: 4% Bentonite + 0.4% Econolite + 0.2% Halad(R)-322 + 3 lbm/sk Silicalite Compacted + 1.2% HR-5 + 0.125 lbm/sk Poly-E-Flake	485	10%	12.0 ppg	2.31
	Tail	1,000	EXPANDACEM (TM) SYSTEM: 0.2% Econolite + 0.3% Versaset + 0.9% HR-5 + 0.3% Super CBL + 0.2% Halad(R)-322 + 0.125 lbm/sk Poly-E-Flake	91	10%	12.5 ppg	1.91
PRODUCTION LINER		2,925	EXTENDACEM (TM) SYSTEM: 0.3% Super CBL + 0.1% SA-1015 + 0.3% Halad(R)-413 + 0.5% SCR-100 + 0.125 lbm/sk Poly-E-Flake + 3 lbm/sk Silicalite Compacted + 20% SSA-1	236	25%	14.20	1.47

FLOAT EQUIPMENT & CENTRALIZERS	
CONDUCTOR	PDC drillable guide shoe, 1 joint, PDC drillable float collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing.
SURFACE	PDC drillable guide shoe, 1 joint casing, PDC drillable float collar & Stage collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing & every 3rd joint thereafter.
INTERMEDIATE	PDC drillable 10M,P-110 float shoe, 1 joint, PDC drillable 10M, P-110 float collar. Thread lock all float equipment. Maker joint at 8,700'.
LINER	Float shoe, 1 joint, float collar. Thread lock all FE. Maker joints every 1000'.

PROJECT ENGINEER(S): Brad MacAfee 713-997-6383

MANAGER: Tommy Gaydos

EP ENERGY E&P COMPANY, L.P.
LAKE FORK RANCH 4-13B4
SECTION 13, T2S, R4W, U.S.B.&M.

PROCEED WEST ON PAVED STATE HIGHWAY 87 FROM THE INTERSECTION OF HIGHWAY 87 WITH 15500 WEST STREET IN ALTAMONT, UTAH APPROXIMATELY 2.40 MILES TO AN INTERSECTION;

TURN LEFT AND TRAVEL SOUTHEASTERLY ON A GRAVEL ROAD 0.85 MILES TO AN INTERSECTION;

TURN LEFT AND TRAVEL EASTERLY THEN SOUTHEASTERLY 3.06 MILES ON A GRAVEL ROAD TO THE ACCESS ROAD;

FOLLOW FLAGS SOUTHEASTERLY APPROXIMATELY 0.26 MILES TO THE PROPOSED WELL LOCATION.

TOTAL DISTANCE FROM ALTAMONT, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 6.57 MILES.

CONFIDENTIAL


RECEIVED: December 05, 2013

EP ENERGY E&P COMPANY, L.P.**FIGURE #2**

LOCATION LAYOUT FOR
LAKE FORK RANCH 4-13B4
SECTION 13, T2S, R4W, U.S.B.&M.
2569' FNL, 2526' FWL

1"=40'
X-SECTION
SCALE
1"=80'

NOTE: ALL CUT/FILL
SLOPES ARE 1½:1
UNLESS OTHERWISE
NOTED



APPROXIMATE YARDAGES

TOTAL CUT (INCLUDING PIT) = 16,856 CU. YDS.

PIT CUT = 4865 CU. YDS.



TOPSOIL STRIPPING: (6") = 3180 CU. YDS.

REMAINING LOCATION CUT = 8811 CU. YDS.

TOTAL FILL = 7869 CU. YDS.

LOCATION SURFACE GRAVEL=1653 CU. YDS. (4" DEEP)

ACCESS ROAD GRAVEL=372 CU. YDS.



JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975
DUCHESNE, UTAH 84021
(435) 738-5352

6 NOV 2013





01-121-483

RECEIVED: December 05, 2013

EP ENERGY E&P COMPANY, L.P.**FIGURE #3**

LOCATION LAYOUT FOR
LAKE FORK RANCH 4-13B4
SECTION 13, T2S, R4W, U.S.B.&M.
2569' FNL, 2526' FWL

SCALE: 1"=80'
0 80




JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975
DUCHESNE, UTAH 84021
(435) 738-5352

6 NOV 2013



01-121-483

RECEIVED: December 05, 2013



EP ENERGY E&P COMPANY, L.P.**WELL LOCATION****LAKE FORK RANCH 4-13B4**

LOCATED IN THE SE¼ OF THE NW¼ OF
SECTION 13, T2S, R4W, U.S.B.&M.
DUCHESNE COUNTY, UTAH



NOTE:
NAD27 VALUES FOR
WELL POSITION:
LAT: 40.307799631° N
LONG: 110.284226522° W

LEGEND AND NOTES

◆ CORNER MONUMENTS FOUND AND USED
BY THIS SURVEY

THE GENERAL LAND OFFICE (G.L.O.) PLAT WAS
USED FOR REFERENCE AND CALCULATIONS AS
WAS THE U.S.G.S. MAP

THIS SURVEY WAS PERFORMED USING GLOBAL
POSITIONING SYSTEM PROCEDURES AND EQUIPMENT

THE BASIS OF BEARINGS IS GEODETIC NORTH DERIVED
FROM G.P.S. OBSERVATIONS AT A CONTROL POINT
LOCATED AT LAT. 40°21'33.56882\"N AND
LONG. 110°16'31.53266\"W USING THE UTAH
STATE G.P.S. VIRTUAL REFERENCE STATION CONTROL
NETWORK MAINTAINED AND OPERATED BY THE
AUTOMATED GEOGRAPHIC REFERENCE CENTER

BASIS OF ELEVATIONS: NAVD 88 DATUM USING
THE UTAH REFERENCE NETWORK CONTROL SYSTEM


19 NOV 2013

6 NOV 2013


01-121-483

SURVEYOR'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM THE FIELD
NOTES AND ELECTRONIC DATA COLLECTOR FILES OF AN ACTUAL
SURVEY PERFORMED BY ME, OR UNDER MY PERSONAL SUPERVISION,
DURING WHICH THE SHOWN MONUMENTS WERE FOUND OR REESTABLISHED.




JERRY D. ALLRED, REGISTERED LAND SURVEYOR,
CERTIFICATE NO. 148951 (UTAH)



JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975
DUCHESNE, UTAH 84021
(435) 738-5352


RECEIVED: December 05, 2013


**LEGEND:**

PROPOSED WELL LOCATION

01-128-483


JERRY D. ALLRED & ASSOCIATES
 SURVEYING CONSULTANTS

 1235 NORTH 700 EAST--P.O. BOX 975
 DUCHESNE, UTAH 84021
 (435) 738-5352
**EL PASO E&P COMPANY, L.P.**
 LAKE FORK RANCH 4-13B4
 SECTION 13, T2S, R4W, U.S.B.&M.
 2569' FSL 2526' FWL
TOPOGRAPHIC MAP "A"
 SCALE: 1"=10,000'
 6 NOV 2013
RECEIVED: December 05, 2013

**LEGEND:**


- PROPOSED WELL LOCATION
- PROPOSED ACCESS ROAD
- EXISTING GRAVEL ROAD

01-128-483



JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975
DUCHESTER, UTAH 84021
(435) 738-5352

**EP ENERGY E&P COMPANY, L.P.**


LAKE FORK RANCH 4-13B4
SECTION 13, T2S, R4W, U.S.B.&M.

2569' FNL 2526' FWL

TOPOGRAPHIC MAP "B"

SCALE: 1"=2000'
6 NOV 2013


RECEIVED: December 05, 2013


**LEGEND:**

PROPOSED WELL LOCATION

2-25C6

01-128-483


JERRY D. ALLRED & ASSOCIATES
 SURVEYING CONSULTANTS

 1235 NORTH 700 EAST--P.O. BOX 975
 DUCHESNE, UTAH 84021
 (435) 738-5352
**EP ENERGY E&P COMPANY, L.P.**
 LAKE FORK RANCH 4-13B4
 SECTION 13, T2S, R4W, U.S.B.&M.

2569' FNL 2526' FWL

TOPOGRAPHIC MAP "C"
 SCALE: 1"=2000'
 6 NOV 2013
RECEIVED: December 05, 2013

AFFIDAVIT OF DAMAGE SETTLEMENT AND RELEASE

Jacquelyn L. Lynch personally appeared before me, and, being duly sworn, deposes and says:

1. My name is Jacquelyn L. Lynch. I am a Landman for EP Energy E&P Company, L.P., whose address is 1001 Louisiana St., Houston, Texas 77002 ("EP Energy").
2. EP Energy is the operator of the proposed Lake Fork Ranch 4-13B4 well (the "Well") to be located in the SE/4NW/4 of Section 13, Township 2 South, Range 4 West, USM, Duchesne County, Utah (the "Drillsite Location"). The surface owners of the Drillsite Location are Myrin Ranch, Inc. and Lake Fork Ranch, Inc (collectively, "the Surface Owners"). Myrin Ranch, Inc. is located at HC 65 Box 30, Altamont, UT 84001, their representative can be contacted at (435) 454-3494. Lake Fork Ranch is located at HC 65 Box 510048, Mountain Home, Utah 84051, their representative can be contacted at (435) 454-3546.
3. EP Energy and the Surface Owners have entered into a Damage Settlement and Release Agreement dated November 18, 2013 and November 7, 2013, respectively, to cover any and all injuries or damages of every character and description sustained by the Surface Owners or Surface Owners' property as a result of operations associated with the drilling of the Well.

FURTHER AFFIANT SAYETH NOT.


Jacquelyn L. Lynch

ACKNOWLEDGMENT

STATE OF TEXAS

§

COUNTY OF HARRIS


§

§

Sworn to and subscribed before me on this 18th day of November, 2013, by Jacquelyn L. Lynch, as Landman for EP Energy E&P Company, L.P., a Delaware limited partnership.


NOTARY PUBLIC

My Commission Expires:



EP Energy E&P Company, L.P.

Related Surface Information

1. **Current Surface Use:**

- Livestock Grazing and Oil and Gas Production.

2. **Proposed Surface Disturbance:**

- The road will be crown and ditch. Water wings will be constructed on the access road as needed.
- The topsoil will be windrowed and re-spread in the borrow area.
- New road to be constructed will be approximately .26 miles in length and 66 feet wide.
- All equipment and vehicles will be confined to the access road, pad and area specified in the APD.

3. **Location Of Existing Wells:**

- Existing oil, gas wells within one (1) mile radius of proposed well are provided in EXHIBIT C.

4. **Location And Type Of Drilling Water Supply:**

- Drilling water: Duchesne City Water

5. **Existing/Proposed Facilities For Productive Well:**

- There are no existing facilities that will be utilized for this well.
- A pipeline corridor .26 miles will parallel the proposed access road. The corridor will contain one 4 inch gas line and one 2 inch gas line and one 2 inch Salt Water disposal line. Rehabilitation of unneeded, previously disturbed areas will consist of backfilling and contouring the reserve pit area; backsloping and contouring all cut and fill slopes. These areas will be reseeded. Refer to plans for reclamation of surface for details.
- Upgrade and maintain access roads and drainage control structures (e.g., culverts, drainage dips, ditching, etc.) as necessary to prevent soil erosion and accommodate safe, year-round traffic.

6. **Construction Materials:**

- Native soil from road and location will be used for construction materials along with gravel and/or scoria road base material. In the event that conditions should necessitate graveling of all or part of the access road and location, surfacing materials will be purchased from commercial suppliers in the marketing area.

7. **Methods For Handling Waste Disposal:**

- The reserve pit will be designed to prevent the collection of surface runoff and will be constructed with a minimum of ½ the total depth below the original ground surface on the lowest point with the pit. The pit will be lined with a 20-mil polyethylene to prevent leakage of fluids. The liner will be rolled into place and secured at the ends, i.e. buried on top of the pit berms. Prior to use, the reserve pit will be fenced on three sides; the fourth side will be fenced at the time the rig is removed. Drilling fluids, cuttings and produced water will be contained in the reserve pit (trash will be placed in the trash cage). Fluids in the reserve pit will be allowed to evaporate prior to pit burial.
- Garbage and other trash will be contained in the portable trash cage and hauled off the location to an authorized disposal site. Any trash on the pad will be cleaned up prior to the rig moving off location and hauled to an authorized disposal site.
- Sewage will be handled in Portable Toilets.
- Produced water will be placed in the reserve pit for a period not to exceed ninety days after initial production. Any hydrocarbons produced during completion work will be contained in test tanks and removed from the location at a later date.
- Water from the reserve pit may be used for drilling of additional wells. The water will be trucked along access roads as approved in pertinent APD's

8. **Ancillary Facilities:**

- There will be no ancillary facilities associated with this project.

9. **Surface Reclamation Plans:**

Backfilling of the pits will be done when dry. In the event of a dry hole, the location will be re-contoured, the topsoil will be distributed evenly over the entire location, and the seedbed prepared.

- Seed will be planted after September 15th, and prior to ground frost, or seed will be planted after the frost has left and before May 15th. Slopes to steep for machinery will be hand broadcast and raked with twice the specified amount of seed.
 1. The construction program and design are on the attached cut, fill and cross sectional diagrams.
 2. Prior to construction, all topsoil will be removed from the entire site and stockpiled. Topsoil for this site is the first 6 inches of soil materials.
 3. After the location has been reshaped and after redistributing the topsoil, the operator will rip and scarify the drilling platform and access road on the contour, to a depth of at least 12 inches.
- Rehabilitation will begin upon the completion of the drilling. Complete rehabilitation will depend on weather conditions and the amount of time required to dry the reserve pit.
 1. All rehabilitation work including seeding will be completed as soon as weather and the reserve pit conditions are appropriate.
 2. Landowner will be contacted for rehabilitation requirements.

10. **Surface Ownership:**

Myrin Ranch, Inc.
HC 65 Box 30
Altamont, UT 84001
435-454-3494

Lake Fork Ranch, Inc.
HC 65 Box 510048
Mountain Home, UT 84051
435-454-3546

Other Information:

- The surface soil consists of clay, and silt.
- Flora – vegetation consists of the following: Sagebrush, Juniper and prairie grasses.
- Fauna – antelope, deer, coyotes, raptors, small mammals, and domestic grazing animals.
- Current surface uses – Livestock grazing and mineral exploration and production.

• **Operator and Contact Persons:**

Construction and Reclamation:


EP Energy E&P Company, L.P.
Wayne Garner
PO Box 410
Altamont, Utah 84001
435-454-3394 – Office
435-823-1490 – Cell

Regarding This APD

EP Energy E&P Company, L.P.
Maria S. Gomez
1001 Louisiana, Rm 2640A
Houston, Texas 77002
713-997-5038 – Office

Drilling

EP Energy E&P Company, L.P.
Brad MacAfee – Drilling Engineer
1001 Louisiana, Rm 2660D
Houston, Texas 77002
713-997-6383 – office
281-813-0902 – Cell






API Number: 4301352719

Well Name: Lake Fork Ranch 4-13B4

Township: T02.0S Range: R04.0W Section: 13 Meridian: U

Operator: EP ENERGY E&P COMPANY, L.P.

Map Prepared: 12/6/2013
Map Produced by Diana Mason



ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator EP ENERGY E&P COMPANY, L.P.
Well Name Lake Fork Ranch 4-13B4
API Number 43013527190000 **APD No** 9160 **Field/Unit** ALTAMONT
Location: 1/4,1/4 SENW **Sec** 13 **Tw** 2.0S **Rng** 4.0W 2569 FNL 2526 FWL
GPS Coord (UTM) 560764 4462164 **Surface Owner** Lake Fork Ranch

Participants

Brent & Matt Brotherson (surface owners); Nils Myrin (surface owner); Chuck McDonald (BLM); Jared Thacker (EP Energy); Kelsey Carter (Land man for EP); Dennis Ingram (DOGM)

Regional/Local Setting & Topography

The Lake Fork Ranch 4-13B4 stakes up 2.4 miles west of Altamont along Highway 87, then south for approximately 3.0 miles along an existing county road, on bench property just west of the Lake Fork River Drainage on a narrow point. The immediate topography at the proposed well pad is nearly flat but slopes east/southeasterly toward the Lake Fork River, showing 6.7 feet of cut at the northwest corner and eight feet of fill at the southeastern corner. Mountain Home, Altonah, and Altamont are small towns found north of the project; to the west and south is mostly pinion/juniper type habitat with open sagebrush flats utilized for pasture and hay production. The Lake Fork River Drainage cuts through this country in a southeastern direction, paralleling this location approximately a quarter miles to the east; Pigeon Water Creek cuts through this country just south of the location and joins the Lake Fork Drainage several hundred yards to the east of proposed well site. Big Sand Wash Reservoir is the largest body of water in that area and located three miles to the southeast.

Surface Use Plan

Current Surface Use

Grazing
Recreational
Wildlife Habitat

**New Road
Miles**

0.26

Well Pad

Width 360 **Length** 465

Src Const Material

Onsite

Surface Formation

UNTA

Ancillary Facilities N

Closed loop mud system

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands Y

Above two flood plains

Flora / Fauna

Sagebrush, pinion/juniper, rabbit brush, prickly pear cactus; elk, mule deer, mountain lion, bobcat, coyote, rabbit, raccoon, and other smaller mammals native to river bottoms.

Soil Type and Characteristics

Fine-grained reddish blow sand at surface with underlying cobbles on ridge adjacent to river bottoms

Erosion Issues Y

Sedimentation Issues Y

Site Stability Issues N

Drainage Diversion Required? N

Berm Required? Y

Special or more permanent berming south of production tanks to protect Pigeon "Water Creek

Erosion Sedimentation Control Required? Y

Silt fencing needed if toe of fill slopes are near or impact ridge line where it breaks into river drainage

Paleo Survey Run? Y **Paleo Potential Observed?** N **Cultural Survey Run?** Y **Cultural Resources?** N

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet) 20

Distance to Surface Water (feet) 300 to 1000 2

Dist. Nearest Municipal Well (ft) >5280 0

Distance to Other Wells (feet) >1320 0

Native Soil Type High permeability 20

Fluid Type Fresh Water 5

Drill Cuttings Normal Rock 0

Annual Precipitation (inches) 0

Affected Populations 30 to 50 30 to 50

Presence Nearby Utility Conduits Present 15

Final Score 70 1 Sensitivity Level

Characteristics / Requirements

Closed loop mud system because of adjacent canyon wall to north with the Lake Fork River below

Closed Loop Mud Required? Y **Liner Required?** **Liner Thickness** **Pit Underlayment Required?**

Other Observations / Comments

Reserve pit stake number "C" was approximately thirty feet from where narrow ridge drops off into the Lake Fork River Drainage, has fine-grained blow sand at surface and underlying cobbles, closed loop system required, BLM requested Arch and culture surveys, landowner asked BLM what they do if the landowner doesn't want them on their lands, two landowners share surface, both were present, talked about casing program, they wondered about impact of well to ground and river water, special berming requirements for tanks to prevent spills from running down hillside into river bottom country.

Dennis Ingram
Evaluator

2/5/2014
Date / Time

CONFIDENTIAL

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
9160	43013527190000	LOCKED	OW	P	No
Operator	EP ENERGY E&P COMPANY, L.P.		Surface Owner-APD	Lake Fork Ranch	
Well Name	Lake Fork Ranch 4-13B4		Unit		
Field	ALTAMONT		Type of Work	DRILL	
Location	SENW 13 2S 4W U 2569 FNL 2526 FWL GPS Coord (UTM) 560762E 4462164N				

Geologic Statement of Basis

EP proposes to set 600 feet of conductor and 3,300 feet of surface casing both of which will be cemented to surface. The surface and intermediate holes will be drilled utilizing fresh water mud. The estimated depth to the base of moderately saline ground water is 3,000 feet. A search of Division of Water Rights records indicates that there are 9 water wells within a 10,000 foot radius of the proposed location. All water wells are over a mile from the proposed location. These wells range in depth from 31 to 550 feet. Listed use is domestic, irrigation, industrial and stock watering. The wells in this area probably produce water from the Duchesne River Formation and associated alluvium. Only one well exceeds 500 feet. The proposed casing and cement program should adequately protect the highly used Duchesne River aquifer.

Brad Hill
APD Evaluator

3/4/2014
Date / Time

Surface Statement of Basis

The surface at the Lake Fork Ranch 4-13B4 slopes to the east, southeast along a narrow ridge top overlooking the Lake Fork River Drainage to the north and Pigeon Water Creek to the south. The proposed reserve pit corner "C" is staked approximately thirty feet from the south rim of the river canyon wall. The soils are fine-grained blow sand with underlying cobbles which doesn't provide enough stability to assure the proposed reserve pit will not leak out the canyon wall. Therefore, a closed loop mud system shall be required on this pad to protect adjacent lands.

The production tanks are planned for the south side of the location near the ridgeline overlooking Pigeon Water Creek. Therefore, the operator needs to install special, more permanent berming around the south side of the location like utilized in other sensitive areas to prevent any potential spills from entering creek bottom.

A presite was scheduled and performed on the Lake Fork Ranch 4-13B4 on February 5, 2014 to take input and address issues regarding the construction and drilling of this well. This proposed well pad is staked across two different landowners, who were both invited to the presite and did attend. EP Energy and both landowners have entered into a surface owner agreement. This well is a split estate well having private minerals and Tribal minerals, therefore Chuck McDonald with the BLM was invited to address federal concerns. McDonald request an Arch survey and that the surface equipment be painted either Juniper Green or Olive Black. No other issues were noted at the presite.

Dennis Ingram
Onsite Evaluator

2/5/2014
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A closed loop mud circulation system is required for this location.
Surface	The well site shall be bermed to prevent fluids from leaving the pad. Special berming requirements around tanks or outside of location to prevent spills from running downhill into adjacent river bottom country (Pigeon Water Creek).

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 12/5/2013

API NO. ASSIGNED: 43013527190000

WELL NAME: Lake Fork Ranch 4-13B4

OPERATOR: EP ENERGY E&P COMPANY, L.P. (N3850)

PHONE NUMBER: 713 997-5038

CONTACT: Maria S. Gomez

PROPOSED LOCATION: SENW 13 020S 040W

Permit Tech Review: ☒

SURFACE: 2569 FNL 2526 FWL

Engineering Review: ☒

BOTTOM: 2569 FNL 2526 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.30778

LONGITUDE: -110.28495

UTM SURF EASTINGS: 560762.00

NORTHINGS: 4462164.00

FIELD NAME: ALTAMONT

LEASE TYPE: 2 - Indian

LEASE NUMBER: Ute 1420H621743

PROPOSED PRODUCING FORMATION(S): GREEN RIVER(LWR)-WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

LOCATION AND SITING:

☒ PLAT☒ R649-2-3.☒ Bond: INDIAN - RLB0009692

Unit:

☐ Potash☐ R649-3-2. General☐ Oil Shale 190-5☐ R649-3-3. Exception☐ Oil Shale 190-3☒ Drilling Unit☐ Oil Shale 190-13☒ Water Permit: Duchesne City

Board Cause No: Cause 139-84

☐ RDCC Review:

Effective Date: 12/31/2008

☒ Fee Surface Agreement

Siting: 660' Fr Ext. U Bdry & 1320' Fr Other Wells

☐ Intent to Commingle☐ R649-3-11. Directional Drill

Commingle Approved

Comments: Presite Completed

Stipulations: 4 - Federal Approval - bhill
5 - Statement of Basis - bhill
8 - Cement to Surface -- 2 strings - hmacdonald
12 - Cement Volume (3) - hmacdonald

RECEIVED: April 23, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Lake Fork Ranch 4-13B4

API Well Number: 43013527190000

Lease Number: Ute 1420H621743

Surface Owner: FEE (PRIVATE)

Approval Date: 4/23/2014

Issued to:

EP ENERGY E&P COMPANY, L.P., 1001 Louisiana, Houston, TX 77002

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-84. The expected producing formation or pool is the GREEN RIVER(LWR)-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volumes for the 13 3/8" and 9 5/8" casing strings shall be determined from actual hole diameters in order to place cement from the pipe setting depths back to the surface.

Cement volume for the 7" intermediate string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 2800' MD as indicated in the submitted drilling plan and tail to 500' above the top of Lower Green River.

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

RECEIVED

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APR 16 2014FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

BLM Vernal UT

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 1420H621743
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator EL PASO E&P COMPANY LP Contact: MARIA GOMEZ E-Mail: maria.gomez@epenergy.com		7. If Unit or CA Agreement, Name and No.
3a. Address 1001 LOUISIANA HOSUTON, TX 77002	3b. Phone No. (include area code) Ph: 713-997-5038	8. Lease Name and Well No. LAKE FORK RANCH 4-13B4
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENW 2569FNL 2526FWL At proposed prod. zone SENW 2569FNL 2526FWL		9. API Well No. 4301352719
14. Distance in miles and direction from nearest town or post office*		10. Field and Pool, or Exploratory ALTAMONT
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No. of Acres in Lease 280.00	11. Sec., T., R., M., or Blk. and Survey or Area Sec 13 T2S R4W Mer UBM
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1100	19. Proposed Depth 13325 MD 13325 TVD	12. County or Parish DUCHESNE
21. Elevations (Show whether DF, KB, RT, GL, etc. 6059 GL	22. Approximate date work will start 06/01/2014	13. State UT
23. Estimated duration 60		17. Spacing Unit dedicated to this well 640.00
24. Attachments		20. BLM/BIA Bond No. on file RLB0009692
		23. Estimated duration 60

DIV. OF OIL, GAS & MINING

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) MARIA GOMEZ Ph: 713-997-5038	Date 04/16/2014
Title PRINCIPAL REGULATORY ANALYST		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date JUN 03 2014
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #242508 verified by the BLM Well Information System
For EL PASO E&P COMPANY LP, sent to the Vernal
Committed to AFMSS for processing by ROBIN R. HANSEN on 04/21/2014 ()

NOTICE OF APPROVAL

UDOGM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: EL PASO E&P COMPANY LP
Well No: LAKE FORK RANCH 4-13B4
API No: 43-013-52719

Location: SENW, Sec. 13, T2S, R4W
Lease No: 14-20-H62-1743
Agreement: N/A

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov .
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

Well Number: Lake Fork Ranch 4-13B4

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COA's)**

- Paint all production facilities and equipment, not otherwise regulated (OSHA, etc.), Juniper Green.
- All areas of disturbance (including surface pipelines) must have appropriate surface use agreements or approvals in place with the proper owner and/or agency before such action is started.
- The conditions of approval, as set forth by those owners and/or agencies, shall be adhered to.
- Stationary internal combustion engines would comply with the following emission standards: 2 g/bhp-hr of NO_x for engines less than 300 HP and 1 g/bhp-hr of NO_x for engines over 300 HP.
- Either no or low bleed controllers would be installed on pneumatic pumps, actuators or other pneumatic devices.
- VOC venting controls or flaring would be utilized for oil or gas atmospheric storage tanks.
- VOC venting controls or flaring would be used for glycol dehydration and amine units.
- Where feasible, green completion would be used for well completion, re-completion, venting, or planned blowdown emissions. Alternatively, use controlled VOC emissions methods with 90% efficiency.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- For the drilling of the surface hole section, operator is required to install an bowl diverter system or rotating head which is connected and discharges to an panic or choke blooie line.
- Pressure integrity test (Pit) or formation integrity test (Fit) shall be performed at the intermediate casing shoe.
- Surface casing cement shall be brought up and into the surface.
- For casing production (partial) liner installation, casing line is to be installed and tested to the standards of Onshore Orders #2. The operator specified casing liner lap overlap interval length is 200 ft.
- Electronic/mechanical mud monitoring equipment shall include from surface casing shoe to TD a ; pit volume totalizer (PVT); stroke counter; and flow sensor.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**

- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well by CD (compact disc). This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.



Alexis Huefner <alexishuefner@utah.gov>

Lake Fork Ranch 4-13B4, API # 43013527190000, Post-24hr Spud Notice

1 message

LANDRIG007 (Patterson 307) <LANDRIG007@epenergy.com>

Tue, Jun 24, 2014 at 10:28 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

CONFIDENTIAL

RE: EP ENERGY

LAKE FORK RANCH 4-13B4

API # 43013527190000

DUCHESNE CO., UTAH

2569 FNL 2526 FWL
SE/W 13 2S 4W

Leon Ross Drilling spudded well today, 06/24/2014 at 0900 HOURS and plan to set >600' of 13 3/8" casing.

Regards,

Eugene Parker

Wellsite Supervisor

Patterson 307

713-997-1255

CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

SENW 5-13 TOSS ROY W

Lake Fork Ranch 4-13B4, API # 43013527190000, Post-24hr Spud Notice

1 message

LANDRIG007 (Patterson 307) <LANDRIG007@epenergy.com>

Tue, Jun 24, 2014 at 10:28 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

RE: EP ENERGY

LAKE FORK RANCH 4-13B4

API # 43013527190000

DUCHESNE CO., UTAH

Leon Ross Drilling spudded well today, 06/24/2014 at 0900 HOURS and plan to set >600' of 13 3/8" casing.

Regards,

Eugene Parker

Wellsite Supervisor

Patterson 307

713-997-1255

CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

SE NW 5-13 T029 R04W

EP Energy - Lake Fork Ranch 4-13B4 - API # 43013527190000

1 message

Lease # UTE 1420H 621743

LANDRIG007 (Patterson 307) <LANDRIG007@epenergy.com>

Fri, Jul 4, 2014 at 10:56 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

Be advised subject well was spudded @ 17:00 on 7/3/14 . This e-mail serves as 24 hr post notification of spud.

Darryl Reeder

EP Energy

Patterson 307

Rig Office: 713-997-1255

EP ENERGY

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

SE NW 5-13 T2S R24W

24 hr Notice, Run & Cement 7" Casing on LAKE FORK RANCH 4-13B4

1 message

LEASE # UTE 1420H621743

LANDRIG007 (Patterson 307) <LANDRIG007@epenergy.com>

Mon, Jul 14, 2014 at 5:54 PM

To: "ut_vn_opreport@blm.gov" <ut_vn_opreport@blm.gov>, "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

RE: EP ENERGY
LAKE FORK RANCH 4-13B4
API # 43013527190000
LEASE SERIAL # 1420H621743
DUCHESNE COUNTY, UTAH

We plan to run and cement 10,640' of 7", 29#, HCP-110, LTC Intermediate casing. Casing run should begin approximately 1800 hours, 07/15/2014.

Regards,
Eugene Parker
Well Site Supervisor
Patterson 307
713-997-1255

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.



CONFIDENTIAL
Carol Daniels <caroldaniels@utah.gov>

SENU 5-13 T02S R04W

EP Energy - Lake Fork Ranch 4-13B4 - API # 43013527190000

1 message

LEASE # UTE 14204621743

LANDRIG007 (Patterson 307) <LANDRIG007@epenergy.com>

Tue, Jul 8, 2014 at 6:55 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

Be advised we have TD'd surface on subject well @ 5,458' . We will run and cement 9 5/8" surface casing tonight as previously reported. We will commence NU & test BOPE operations tomorrow AM. This e-mail serves as 24 notification of BOPE test

Regards,

Darryl Reeder

EP Energy

Patterson 307

Rig Office: 713-997-1255

EP ENERGY

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

SENW S-13 T02S P044

24 hr Notice, SIDETRACK the LAKE FORK RANCH 4-13B4

1 message

LANDRIG007 (Patterson 307) <LANDRIG007@epenergy.com>

Sun, Jul 20, 2014 at 11:27 AM

To: "ut_vn_opreport@blm.gov" <ut_vn_opreport@blm.gov>, "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Evans, Perry (Contractor)" <Perry.Evans@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "Morales, Lisa" <Lisa.Morales@epenergy.com>

RE: EP ENERGY
LAKE FORK RANCH 4-13B4
API # 43013527190000
LEASE SERIAL # 1420H621743
DUCHESNE COUNTY, UTAH

We plan to begin SIDETRACKING approximately 1100 HOURS, 07/21/2014.

Regards,
Eugene Parker
Well Site Supervisor
Patterson 307
713-997-1255

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Ute 1420H621743			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute			
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY, L.P.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1001 Louisiana, Houston, TX, 77002		8. WELL NAME and NUMBER: Lake Fork Ranch 4-13B4			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2569 FNL 2526 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 13 Township: 02.0S Range: 04.0W Meridian: U		9. API NUMBER: 43013527190000			
9. FIELD and POOL or WILDCAT: ALTAMONT		COUNTY: DUCHESNE			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/23/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text" value="Initial Completion"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text" value="Initial Completion"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text" value="Initial Completion"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. EP plans to complete in the Wasatch. Please see attached for details.					
Accepted by the Utah Division of Oil, Gas and Mining August 28, 2014 Date: _____ By: <u>Derek Quist</u>					
NAME (PLEASE PRINT) Maria S. Gomez		PHONE NUMBER 713 997-5038			
SIGNATURE N/A		TITLE Principal Regulatory Analyst			
DATE 8/18/2014					

Lake Fork Ranch 4-13B4

Initial Completion

API # : 43013527190000

The following precautions will be taken until the RCA for the Conover is completed:

1. Review torque turning and running of the 7" and 5" liner of anomalies.
2. Test and chart casing for 30 minutes, noting pressure if any on surface casing.
3. Test all lubricators, valves and BOP's to working pressure.
4. Wellhead isolation tools will continue to be used to isolate the wellhead during the frac.
5. Monitor the surface casing during frac:
 - a. Lay a flowline to the flow back tank and keep the valve open.
 - b. This line will remain in place until a wire line set retrievable packer is in place isolating the 5" casing from the 7" after the frac.
6. 2 7/8" tubing will be run to isolate the 7" casing during the flow back of the well.
7. Well pressure and annulus pressure would be monitored during this time until the well is ready for pump.

Completion Information (Wasatch Formation)

Stage #1	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~13010' – 13252' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~130000 # of Power Prop 20/40. Total clean water volume is 118580 gals.
Stage #2	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~12714' – 12979' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~130000 # of Power Prop 20/40. Total clean water volume is 118138 gals.
Stage #3	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~12481' – 12682' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~130000 # of Power Prop 20/40. Total clean water volume is 117791 gals.
Stage #4	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~12205' – 12442' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~130000 # of Power Prop 20/40. Total clean water volume is 117379 gals.
Stage #5	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~11963' – 12176' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~130000 # of Power Prop 20/40. Total clean water volume is 117018 gals.

Stage #6

RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~11690' – 11934' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of Power Prop 20/40. Total clean water volume is 128844 gals.

RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~' – ' with ~ gallons of 15% HCL acid, ~ # of 100 mesh sand and ~ # of . Total clean water volume is gals.

Stimulation Summary


	Top Perf	Btm. Perf	Gross Interval	Plug Depth	Net Perf Length	Total Shots	Perf Intervals	Type of Prop	Lbs of Prop	Lbs/ft	Lbs of 100 Mesh	Gals of HCL (15%)	Gals of Clean H2O	Gals of Slurry
Stage #1	13,010	13,252	242	NA	22	66	17	Power Prop 20/40	130,000	537	3,000	5,000	118,580	133,602
Stage #2	12,714	12,979	265	12,989	23	69	17	Power Prop 20/40	130,000	491	3,000	5,000	118,138	133,161
Stage #3	12,481	12,682	201	12,692	20	60	16	Power Prop 20/40	130,000	647	3,000	5,000	117,791	132,813
Stage #4	12,205	12,442	237	12,452	22	66	17	Power Prop 20/40	130,000	549	3,000	5,000	117,379	132,401
Stage #5	11,963	12,176	213	12,186	21	63	17	Power Prop 20/40	130,000	610	3,000	5,000	117,018	132,040
Stage #6	11,690	11,934	244	11,944	23	69	17	Power Prop 20/40	150,000	615	3,000	5,000	128,844	145,373
Average per Stage			234		22	66	17		133,333	575	3,000	5,000	119,625	134,899
Totals per Well			1,402		131	393	101		800,000		18,000	30,000	717,750	809,392



Pre-Completion Wellbore Schematic

Well Name: **Lake Fork Ranch 4-13B4**
Company Name: **EP Energy**
Field, County, State: **Altamont, Duchesne, Utah**
Surface Location: **Lat: 40°18'27.917" N Long: 110°17'05.777" W**
Producing Zone(s): **Wasatch**

Last Updated: **8/11/2014**
By: **Jarrold Kent**
TD: **13,325**
API: **43013527190000**
AFE: **162113**





Post-Completion Wellbore Schematic

Well Name: **Lake Fork Ranch 4-13B4**
 Company Name: **EP Energy**
 Field, County, State: **Altamont, Duchesne, Utah**
 Surface Location: **Lat: 40°18'27.917" N Long: 110°17'05.777" W**
 Producing Zone(s): **Wasatch**


Last Updated: **8/18/2014**

By: **Jarrod Kent**

TD: **13,325**

API: **43013527190000**

AFE: **162113**



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MININGAMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG						5. LEASE DESIGNATION AND SERIAL NUMBER:					
						6. IF INDIAN, ALLOTTEE OR TRIBE NAME					
						7. UNIT or CA AGREEMENT NAME					
						8. WELL NAME and NUMBER:					
1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____						9. API NUMBER:					
b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____						10 FIELD AND POOL, OR WILDCAT					
2. NAME OF OPERATOR:						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:					
3. ADDRESS OF OPERATOR: CITY _____ STATE _____ ZIP _____						PHONE NUMBER: _____		12. COUNTY		13. STATE UTAH	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:						17. ELEVATIONS (DF, RKB, RT, GL):					
14. DATE SPUDDED:		15. DATE T.D. REACHED:		16. DATE COMPLETED: ABANDONED <input type="checkbox"/> READY TO PRODUCE <input type="checkbox"/>		21. DEPTH BRIDGE MD PLUG SET: TVD					
18. TOTAL DEPTH: MD TVD		19. PLUG BACK T.D.: MD TVD		20. IF MULTIPLE COMPLETIONS, HOW MANY? *		23. WAS WELL CORED? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit copy)					
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)											
24. CASING AND LINER RECORD (Report all strings set in well)											
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED		
25. TUBING RECORD											
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)			
26. PRODUCING INTERVALS					27. PERFORATION RECORD						
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS			
(A)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>			
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>			
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>			
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>			
28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. See attached for further information on #27 & #28.											
DEPTH INTERVAL		AMOUNT AND TYPE OF MATERIAL									
29. ENCLOSED ATTACHMENTS: All logs are submitted to UDOGM by vendor.								30. WELL STATUS:			
<input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS				<input type="checkbox"/> GEOLOGIC REPORT		<input type="checkbox"/> DST REPORT		<input type="checkbox"/> DIRECTIONAL SURVEY			
<input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION				<input type="checkbox"/> CORE ANALYSIS		<input type="checkbox"/> OTHER: _____					

31. INITIAL PRODUCTION**INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)**33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) _____ TITLE _____

SIGNATURE _____ DATE _____

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Attachment to Well Completion Report**Form 8 Dated September 28, 2014****Well Name: Lake Fork Ranch 4-13B4****Items #27 and #28 Continued****27. Perforation Record**

Interval (Top/Bottom – MD)	Size	No. of Holes	Perf. Status
11963'-12174'	.37	63	Open
11691'-11934'	.37	69	Open

28. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
12204'-12441'	5000 gal acid, 3000# 100 mesh, 130030# 20/40 PowerProp
11963'-12174'	5000 gal acid, 3000# 100 mesh, 130000# 20/40 PowerProp
11691'-11934'	5000 gal acid, 4860# 100 mesh, 150000# 20/40 PowerProp
10513'-10515'	Squeezed thru EZSV w/250 sx/287.5 slurry



Company: EP Energy
Well: Lake Fork Ranch 4-13B4
Location: Duchesne, UT
Rig: Patterson 307

Job Number:
Mag Decl.:
Dir Driller:
MWD Eng:

Calculation Method Minimum Curvature
Proposed Azimuth 0.00
Depth Reference KB
Tie Into: Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)	Distance (ft)	Direction Azimuth			
Tie In	0.00	0.00	0.00										
1	696.00	0.30	150.62	696.00	696.00	-1.59	1.59 S	0.89 E	1.82	150.62	0.04	0.04	21.64
2	792.00	1.26	130.11	96.00	791.99	-2.49	2.49 S	1.82 E	3.08	143.73	1.03	1.00	-21.36
3	888.00	2.53	123.68	96.00	887.93	-4.34	4.34 S	4.40 E	6.18	134.65	1.34	1.32	-6.70
4	984.00	4.15	118.75	96.00	983.77	-7.19	7.19 S	9.20 E	11.68	127.99	1.71	1.69	-5.14
5	1080.00	4.80	120.48	96.00	1079.47	-10.90	10.90 S	15.71 E	19.12	124.74	0.69	0.68	1.80
6	1175.00	5.41	120.62	95.00	1174.10	-15.19	15.19 S	22.99 E	27.56	123.46	0.64	0.64	0.15
7	1271.00	6.36	122.39	96.00	1269.59	-20.35	20.35 S	31.38 E	37.40	122.96	1.01	0.99	1.84
8	1366.00	6.35	127.94	95.00	1364.01	-26.40	26.40 S	39.96 E	47.89	123.45	0.65	-0.01	5.84
9	1461.00	6.10	132.83	95.00	1458.45	-33.06	33.06 S	47.81 E	58.12	124.66	0.62	-0.26	5.15
10	1557.00	5.78	135.36	96.00	1553.93	-39.96	39.96 S	54.94 E	67.94	126.03	0.43	-0.33	2.64
11	1652.00	4.80	138.95	95.00	1648.53	-46.37	46.37 S	60.92 E	76.55	127.28	1.09	-1.03	3.78
12	1748.00	4.55	140.33	96.00	1744.21	-52.33	52.33 S	65.98 E	84.21	128.41	0.29	-0.26	1.44
13	1842.00	5.03	140.86	94.00	1837.88	-58.39	58.39 S	70.97 E	91.90	129.45	0.51	0.51	0.56
14	1936.00	5.02	134.76	94.00	1931.52	-64.48	64.48 S	76.49 E	100.04	130.13	0.57	-0.01	-6.49
15	2032.00	4.78	121.34	96.00	2027.17	-69.52	69.52 S	82.89 E	108.18	129.99	1.22	-0.25	-13.98
16	2128.00	4.89	115.06	96.00	2122.83	-73.34	73.34 S	90.01 E	116.10	129.17	0.56	0.11	-6.54
17	2224.00	5.34	114.74	96.00	2218.45	-76.94	76.94 S	97.77 E	124.41	128.20	0.47	0.47	-0.33
18	2319.00	5.91	115.19	95.00	2312.99	-80.87	80.87 S	106.21 E	133.50	127.29	0.60	0.60	0.47
19	2415.00	5.18	114.05	96.00	2408.54	-84.74	84.74 S	114.64 E	142.56	126.47	0.77	-0.76	-1.19
20	2510.00	4.70	111.23	95.00	2503.19	-87.90	87.90 S	122.19 E	150.52	125.73	0.57	-0.51	-2.97
21	2606.00	3.93	114.58	96.00	2598.91	-90.69	90.69 S	128.85 E	157.56	125.14	0.84	-0.80	3.49
22	2702.00	3.00	122.78	96.00	2694.74	-93.42	93.42 S	133.95 E	163.31	124.89	1.10	-0.97	8.54
23	2797.00	2.85	130.39	95.00	2789.61	-96.29	96.29 S	137.84 E	168.14	124.94	0.44	-0.16	8.01
24	2893.00	3.47	131.70	96.00	2885.47	-99.77	99.77 S	141.82 E	173.40	125.13	0.65	0.65	1.36
25	2988.00	3.84	136.81	95.00	2980.27	-104.01	104.01 S	146.15 E	179.38	125.44	0.52	0.39	5.38
26	3084.00	4.55	138.87	96.00	3076.02	-109.22	109.22 S	150.85 E	186.24	125.90	0.76	0.74	2.15
27	3180.00	4.24	142.62	96.00	3171.73	-114.91	114.91 S	155.51 E	193.36	126.46	0.44	-0.32	3.91
28	3276.00	3.60	136.07	96.00	3267.51	-119.90	119.90 S	159.76 E	199.74	126.89	0.81	-0.67	-6.82
29	3371.00	3.39	123.10	95.00	3362.33	-123.58	123.58 S	164.18 E	205.49	126.97	0.86	-0.22	-13.65
30	3466.00	3.62	117.69	95.00	3457.16	-126.51	126.51 S	169.19 E	211.25	126.79	0.42	0.24	-5.69
31	3562.00	4.00	117.50	96.00	3552.94	-129.46	129.46 S	174.84 E	217.55	126.52	0.40	0.40	-0.20
32	3657.00	4.56	118.09	95.00	3647.68	-132.77	132.77 S	181.11 E	224.57	126.24	0.59	0.59	0.62
33	3752.00	4.33	119.88	95.00	3742.39	-136.33	136.33 S	187.55 E	231.87	126.01	0.28	-0.24	1.88
34	3847.00	3.51	118.13	95.00	3837.17	-139.49	139.49 S	193.23 E	238.32	125.83	0.87	-0.86	-1.84
35	3943.00	3.72	118.26	96.00	3932.98	-142.35	142.35 S	198.56 E	244.32	125.64	0.22	0.22	0.14



Company: EP Energy
Well: Lake Fork Ranch 4-13B4
Location: Duchesne, UT
Rig: Patterson 307

Job Number:
Mag Decl.:
Dir Driller:
MWD Eng:

Calculation Method Minimum Curvature
Proposed Azimuth 0.00
Depth Reference KB
Tie Into: Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)	Distance (ft)	Direction Azimuth			
36	4038.00	4.32	121.66	95.00	4027.74	-145.69	145.69 S	204.32 E	250.94	125.49	0.68	0.63	3.58
37	4134.00	3.80	123.73	96.00	4123.50	-149.35	149.35 S	210.05 E	257.73	125.41	0.56	-0.54	2.16
38	4229.00	3.15	121.04	95.00	4218.33	-152.45	152.45 S	214.90 E	263.48	125.35	0.71	-0.68	-2.83
39	4324.00	3.33	117.65	95.00	4313.18	-155.07	155.07 S	219.58 E	268.82	125.23	0.28	0.19	-3.57
40	4419.00	3.85	118.69	95.00	4407.99	-157.88	157.88 S	224.82 E	274.72	125.08	0.55	0.55	1.09
41	4514.00	4.27	119.90	95.00	4502.75	-161.18	161.18 S	230.69 E	281.42	124.94	0.45	0.44	1.27
42	4610.00	4.20	117.74	96.00	4598.49	-164.60	164.60 S	236.90 E	288.47	124.79	0.18	-0.07	-2.25
43	4705.00	4.29	116.10	95.00	4693.23	-167.78	167.78 S	243.17 E	295.43	124.60	0.16	0.09	-1.73
44	4801.00	4.24	115.13	96.00	4788.96	-170.87	170.87 S	249.60 E	302.49	124.39	0.09	-0.05	-1.01
45	4897.00	4.09	110.64	96.00	4884.71	-173.58	173.58 S	256.02 E	309.32	124.14	0.37	-0.16	-4.68
46	4993.00	4.17	108.85	96.00	4980.46	-175.91	175.91 S	262.53 E	316.02	123.83	0.16	0.08	-1.86
47	5089.00	4.73	106.89	96.00	5076.17	-178.19	178.19 S	269.62 E	323.18	123.46	0.60	0.58	-2.04
48	5185.00	4.18	112.25	96.00	5171.88	-180.67	180.67 S	276.64 E	330.41	123.15	0.72	-0.57	5.58
49	5280.00	3.55	126.14	95.00	5266.67	-183.71	183.71 S	282.22 E	336.75	123.06	1.18	-0.66	14.62
50	5383.00	3.67	140.15	103.00	5369.46	-188.12	188.12 S	286.91 E	343.09	123.25	0.86	0.12	13.60
51	5495.00	3.59	142.79	112.00	5481.24	-193.67	193.67 S	291.33 E	349.83	123.61	0.17	-0.07	2.36
52	5590.00	3.18	116.22	95.00	5576.08	-197.20	197.20 S	295.49 E	355.25	123.72	1.69	-0.43	-27.97
53	5686.00	5.14	103.23	96.00	5671.82	-199.36	199.36 S	302.07 E	361.93	123.42	2.25	2.04	-13.53
54	5781.00	6.34	99.26	95.00	5766.35	-201.18	201.18 S	311.39 E	370.72	122.87	1.33	1.26	-4.18
55	5876.00	6.14	92.04	95.00	5860.78	-202.20	202.20 S	321.64 E	379.92	122.16	0.85	-0.21	-7.60
56	5971.00	7.46	102.13	95.00	5955.12	-203.68	203.68 S	332.75 E	390.14	121.47	1.87	1.39	10.62
57	6065.00	6.50	103.26	94.00	6048.42	-206.18	206.18 S	343.89 E	400.97	120.95	1.03	-1.02	1.20
58	6160.00	5.54	105.72	95.00	6142.89	-208.66	208.66 S	353.54 E	410.53	120.55	1.05	-1.01	2.59
59	6256.00	6.02	87.37	96.00	6238.41	-209.68	209.68 S	363.03 E	419.24	120.01	1.98	0.50	-19.11
60	6351.00	7.02	90.82	95.00	6332.80	-209.54	209.54 S	373.81 E	428.54	119.27	1.13	1.05	3.63
61	6446.00	8.35	93.51	95.00	6426.94	-210.04	210.04 S	386.50 E	439.89	118.52	1.45	1.40	2.83
62	6541.00	6.97	95.41	95.00	6521.09	-211.01	211.01 S	399.13 E	451.47	117.86	1.48	-1.45	2.00
63	6636.00	5.67	96.79	95.00	6615.51	-212.11	212.11 S	409.53 E	461.20	117.38	1.38	-1.37	1.45
64	6731.00	5.88	100.40	95.00	6710.03	-213.54	213.54 S	418.97 E	470.25	117.01	0.44	0.22	3.80
65	6825.00	4.93	105.47	94.00	6803.61	-215.49	215.49 S	427.60 E	478.83	116.75	1.13	-1.01	5.39
66	6920.00	4.86	102.38	95.00	6898.27	-217.44	217.44 S	435.47 E	486.74	116.53	0.29	-0.07	-3.25
67	7015.00	6.82	97.64	95.00	6992.77	-219.05	219.05 S	444.99 E	495.98	116.21	2.12	2.06	-4.99
68	7110.00	6.21	104.20	95.00	7087.16	-221.06	221.06 S	455.56 E	506.37	115.89	1.01	-0.64	6.91
69	7205.00	5.90	105.76	95.00	7181.63	-223.65	223.65 S	465.24 E	516.21	115.67	0.37	-0.33	1.64
70	7301.00	8.16	107.25	96.00	7276.90	-227.01	227.01 S	476.50 E	527.81	115.47	2.36	2.35	1.55
71	7395.00	9.38	105.16	94.00	7369.80	-230.99	230.99 S	490.26 E	541.96	115.23	1.34	1.30	-2.22
72	7489.00	10.07	108.63	94.00	7462.45	-235.62	235.62 S	505.45 E	557.67	114.99	0.96	0.73	3.69



Company: EP Energy
Well: Lake Fork Ranch 4-13B4
Location: Duchesne, UT
Rig: Patterson 307

Job Number:
Mag Decl.:
Dir Driller:
MWD Eng:

Calculation Method Minimum Curvature
Proposed Azimuth 0.00
Depth Reference KB
Tie Into: Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)	Distance (ft)	Direction Azimuth			
73	7585.00	8.99	109.90	96.00	7557.12	-240.86	240.86	S 520.45	E 573.48	114.83	1.15	-1.13	1.32
74	7680.00	9.14	110.78	95.00	7650.94	-246.06	246.06	S 534.49	E 588.40	114.72	0.22	0.16	0.93
75	7776.00	8.66	113.58	96.00	7745.78	-251.66	251.66	S 548.24	E 603.24	114.66	0.67	-0.50	2.92
76	7871.00	7.39	119.55	95.00	7839.85	-257.53	257.53	S 560.11	E 616.48	114.69	1.60	-1.34	6.28
77	7967.00	7.28	121.27	96.00	7935.06	-263.73	263.73	S 570.68	E 628.67	114.80	0.26	-0.11	1.79
78	8062.00	9.20	123.46	95.00	8029.08	-271.04	271.04	S 582.16	E 642.16	114.97	2.05	2.02	2.31
79	8158.00	8.89	124.45	96.00	8123.89	-279.47	279.47	S 594.68	E 657.08	115.17	0.36	-0.32	1.03
80	8253.00	8.78	123.13	95.00	8217.76	-287.59	287.59	S 606.80	E 671.50	115.36	0.24	-0.12	-1.39
81	8349.00	7.85	126.59	96.00	8312.75	-295.50	295.50	S 618.20	E 685.20	115.55	1.10	-0.97	3.60
82	8444.00	6.91	130.20	95.00	8406.96	-303.06	303.06	S 627.78	E 697.10	115.77	1.10	-0.99	3.80
83	8538.00	6.20	135.35	94.00	8500.35	-310.32	310.32	S 635.66	E 707.37	116.02	0.98	-0.76	5.48
84	8633.00	5.03	137.32	95.00	8594.89	-317.03	317.03	S 642.09	E 716.09	116.28	1.25	-1.23	2.07
85	8729.00	4.54	143.43	96.00	8690.56	-323.17	323.17	S 647.21	E 723.41	116.53	0.74	-0.51	6.36
86	8825.00	3.95	150.55	96.00	8786.29	-329.10	329.10	S 651.10	E 729.55	116.81	0.82	-0.61	7.42
87	8920.00	4.11	153.01	95.00	8881.06	-334.99	334.99	S 654.25	E 735.03	117.11	0.25	0.17	2.59
88	9016.00	3.64	151.35	96.00	8976.84	-340.73	340.73	S 657.28	E 740.34	117.40	0.50	-0.49	-1.73
89	9111.00	3.33	151.27	95.00	9071.66	-345.79	345.79	S 660.05	E 745.14	117.65	0.33	-0.33	-0.08
90	9207.00	2.98	154.59	96.00	9167.52	-350.49	350.49	S 662.46	E 749.46	117.88	0.41	-0.36	3.46
91	9302.00	3.31	168.95	95.00	9262.37	-355.41	355.41	S 664.04	E 753.18	118.16	0.90	0.35	15.12
92	9398.00	3.65	169.00	96.00	9358.20	-361.13	361.13	S 665.16	E 756.87	118.50	0.35	0.35	0.05
93	9494.00	3.32	174.43	96.00	9454.02	-366.90	366.90	S 666.01	E 760.39	118.85	0.49	-0.34	5.66
94	9589.00	2.79	178.24	95.00	9548.88	-371.95	371.95	S 666.35	E 763.13	119.17	0.60	-0.56	4.01
95	9685.00	2.31	206.20	96.00	9644.79	-376.02	376.02	S 665.57	E 764.44	119.46	1.37	-0.50	29.13
96	9780.00	0.83	245.10	95.00	9739.76	-378.03	378.03	S 664.10	E 764.15	119.65	1.84	-1.56	40.95
97	9876.00	0.83	219.72	96.00	9835.75	-378.86	378.86	S 663.02	E 763.63	119.74	0.38	0.00	-26.44
98	9971.00	1.44	206.21	95.00	9930.73	-380.46	380.46	S 662.06	E 763.59	119.88	0.70	0.64	-14.22
99	10066.00	2.05	186.85	95.00	10025.68	-383.21	383.21	S 661.33	E 764.33	120.09	0.88	0.64	-20.38
100	10161.00	3.01	175.15	95.00	10120.59	-387.39	387.39	S 661.33	E 766.44	120.36	1.14	1.01	-12.32
101	10256.00	3.43	175.18	95.00	10215.44	-392.70	392.70	S 661.78	E 769.53	120.68	0.44	0.44	0.03
102	10351.00	2.78	169.18	95.00	10310.30	-397.80	397.80	S 662.45	E 772.72	120.98	0.76	-0.68	-6.32
103	10447.00	1.90	172.70	96.00	10406.22	-401.66	401.66	S 663.09	E 775.26	121.21	0.93	-0.92	3.67
104	10547.00	1.48	182.28	100.00	10506.18	-404.60	404.60	S 663.25	E 776.92	121.38	0.50	-0.42	9.58
105	10658.00	3.65	239.39	111.00	10617.07	-407.83	407.83	S 660.15	E 775.97	121.71	2.80	1.95	51.45
106	10744.00	3.72	265.23	86.00	10702.90	-409.46	409.46	S 655.02	E 772.47	122.01	1.92	0.08	30.05
107	10862.00	3.11	293.73	118.00	10820.70	-408.49	408.49	S 648.27	E 766.24	122.22	1.51	-0.52	24.15
108	10956.00	1.85	330.68	94.00	10914.62	-406.14	406.14	S 645.19	E 762.38	122.19	2.10	-1.34	39.31
109	11051.00	1.71	346.79	95.00	11009.57	-403.42	403.42	S 644.12	E 760.03	122.06	0.54	-0.15	16.96



Company: EP Energy
Well: Lake Fork Ranch 4-13B4
Location: Duchesne, UT
Rig: Patterson 307

Job Number: _____
Mag Decl.: _____
Dir Driller: _____
MWD Eng: _____

Calculation Method Minimum Curvature
Proposed Azimuth 0.00
Depth Reference KB
Tie Into: Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates			Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')	
							N/S (ft)		E/W (ft)	Distance (ft)	Direction Azimuth				
110	11146.00	1.33	357.37	95.00	11104.54	-400.94	400.94	S	643.75	E	758.39	121.92	0.50	-0.40	11.14
111	11242.00	0.91	3.69	96.00	11200.52	-399.07	399.07	S	643.74	E	757.40	121.80	0.46	-0.44	-368.42
112	11337.00	0.58	13.18	95.00	11295.51	-397.84	397.84	S	643.90	E	756.89	121.71	0.37	-0.35	9.99
113	11432.00	0.35	51.95	95.00	11390.51	-397.20	397.20	S	644.24	E	756.84	121.66	0.40	-0.24	40.81
114	11526.00	0.31	101.49	94.00	11484.51	-397.07	397.07	S	644.71	E	757.18	121.63	0.30	-0.04	52.70
115	11620.00	0.35	98.21	94.00	11578.50	-397.16	397.16	S	645.25	E	757.68	121.61	0.05	0.04	-3.49
116	11716.00	0.55	118.90	96.00	11674.50	-397.43	397.43	S	645.94	E	758.41	121.60	0.27	0.21	21.55
117	11811.00	0.63	146.03	95.00	11769.50	-398.08	398.08	S	646.63	E	759.34	121.62	0.30	0.08	28.56
118	11908.00	0.99	149.30	97.00	11866.49	-399.24	399.24	S	647.36	E	760.57	121.66	0.37	0.37	3.37
119	12005.00	1.20	151.62	97.00	11963.47	-400.86	400.86	S	648.27	E	762.19	121.73	0.22	0.22	2.39
120	12100.00	1.13	146.56	95.00	12058.45	-402.51	402.51	S	649.26	E	763.91	121.80	0.13	-0.07	-5.33
121	12165.00	1.11	149.30	65.00	12123.44	-403.59	403.59	S	649.93	E	765.05	121.84	0.09	-0.03	4.22
122	12194.00	1.24	153.73	29.00	12152.43	-404.11	404.11	S	650.22	E	765.56	121.86	0.55	0.45	15.28
123	12289.00	1.48	166.68	95.00	12247.40	-406.23	406.23	S	650.95	E	767.31	121.97	0.41	0.25	13.63
124	12384.00	1.38	162.13	95.00	12342.37	-408.51	408.51	S	651.59	E	769.06	122.09	0.16	-0.11	-4.79
125	12479.00	1.44	159.24	95.00	12437.35	-410.72	410.72	S	652.36	E	770.88	122.19	0.10	0.06	-3.04
126	12574.00	1.35	158.85	95.00	12532.32	-412.88	412.88	S	653.19	E	772.74	122.30	0.10	-0.09	-0.41
127	12669.00	1.38	155.99	95.00	12627.29	-414.97	414.97	S	654.06	E	774.59	122.39	0.08	0.03	-3.01
128	12763.00	1.49	156.49	94.00	12721.26	-417.12	417.12	S	655.00	E	776.54	122.49	0.12	0.12	0.53
129	12858.00	1.46	167.90	95.00	12816.23	-419.44	419.44	S	655.75	E	778.42	122.60	0.31	-0.03	12.01
130	12953.00	1.49	170.54	95.00	12911.20	-421.84	421.84	S	656.21	E	780.10	122.73	0.08	0.03	2.78
131	13047.00	1.43	171.05	94.00	13005.17	-424.20	424.20	S	656.59	E	781.70	122.87	0.07	-0.06	0.54
132	13142.00	1.60	174.68	95.00	13100.13	-426.69	426.69	S	656.90	E	783.32	123.01	0.21	0.18	3.82
133	13237.00	1.65	176.49	95.00	13195.10	-429.38	429.38	S	657.11	E	784.95	123.16	0.08	0.05	1.91
134	13373.00	1.65	176.49	136.00	13331.04	-433.29	433.29	S	657.35	E	787.30	123.39	0.00	0.00	0.00

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Ute 1420H621743
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well		8. WELL NAME and NUMBER: Lake Fork Ranch 4-13B4
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY, L.P.		9. API NUMBER: 43013527190000
3. ADDRESS OF OPERATOR: 1001 Louisiana , Houston, TX, 77002		9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2569 FNL 2526 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 13 Township: 02.0S Range: 04.0W Meridian: U		COUNTY: DUCHESNE
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/15/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: <input type="text" value="See Below"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="text-align: center; padding: 20px;"> downsize & deepen (corod). See attached for details. </div> <div style="text-align: right; padding: 20px;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 18, 2015 </div>		
NAME (PLEASE PRINT) Maria S. Gomez	PHONE NUMBER 713 997-5038	TITLE Principal Regulatory Analyst
SIGNATURE N/A	DATE 6/16/2015	

CENTRAL DIVISION

ALTAMONT FIELD
LAKE FORK RANCH 4-13B4
LAKE FORK RANCH 4-13B4
WORKOVER LAND

Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

1 General

1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

1.2 Well Information

Well	LAKE FORK RANCH 4-13B4		
Project	ALTAMONT FIELD	Site	LAKE FORK RANCH 4-13B4
Rig Name/No.	NABORS DRILLING/0561	Event	WORKOVER LAND
Start date	5/11/2015	End date	5/16/2015
Spud Date/Time	7/3/2014	UWI	LAKE FORK RANCH 4-13B4
Active datum	KB @6,082.7ft (above Mean Sea Level)		
Afe No./Description	164750/53894 / LAKE FORK RANCH 4-13B4		

2 Summary

2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
5/12/2015	7:00 9:00	2.00	MIRU	01		P		MOVE RIG TO LOCATION, HOLD SAFETY MEETING (TOPIC) MOVING & SPOTTING IN EQUIPMENT MIRU COROD RIG & SPOOL
	9:00 10:00	1.00	PRDHEQ	18		P		BLEED OFF TBG, ON THE 3rd ATTEMPT SCREWED INTO & UNSEATED STANDING VALVE, L/D POLISH ROD & PONY SUBS
	10:00 10:30	0.50	PRDHEQ	18		P		R/U HOTOILER, FLUSH COROD W/ 60 BBLS 2% KCL
	10:30 12:30	2.00	PRDHEQ	39		P		POOH W/ 1018' # 8, 1336' # 7, 1253' # 6, 3619' # 5, 1100' # 7 COROD, L/D 2 1/4" PLUNGER & STANDING VALVE,
	12:30 13:00	0.50	RDMO	02		P		RDMO COROD RIG.
	13:00 14:00	1.00	MIRU	01		P		MIRU NABORS RIG # 1446, X-O TO TBG EQUIPMENT
	14:00 15:30	1.50	PRDHEQ	16		P		N/D B-FLANGE, N/U 10K X 5K SPOOL & 5K BOPS, R/U WORK FLOOR & TONGS,
	15:30 17:00	1.50	PRDHEQ	39		P		POOH W/ 56 JTS 2 7/8", TBG WAS ROD CUT THE WIDTH OF COROD AROUND 1/16" DEEP, RIH W/ 56 JTS 2 7/8", SECURE WELL, SDFD,
5/13/2015	6:00 7:00	1.00	PRDHEQ	28		P		CREW TRAVEL HSM WRITE & REVIEW JSA (TOPIC) BOPS
	7:00 13:00	6.00	PRDHEQ	39		P		CSIP 50 PSI, BLEED OFF GAS, POOH LAY DOWN ROD CUT TBG W/ 251 JTS 2 7/8", 7" TAC, 4 JTS 2 7/8", 4' x 2 7/8" SUB, 2 7/8" PSN, 2' X 2 7/8" SUB, 5 1/2" PBGA, 2 JTS 2 7/8" & 5 3/4" NO/GO, FLUSH TBG AS NEEDED POOH
	13:00 15:30	2.50	SL	32		P		R/U DELSCO, RIH W/ 1-1/2" SINKER BAR TAGGED @ 13346' (SLM), BTM PERFS @ 13,252', PBTD @ 13,325', POOH, R/D DELSCO
	15:30 18:00	2.50	PRDHEQ	24		P		P/U & RIH W/ NEW BHA, 2 3/8" BULL PLUG, 2 JTS 2 3/8", 2 3/8" # 5 DESANDER, 4' X 2 3/8" SUB, 2 3/8" SEAT NIPPLE, P/U 4 NEW JTS 2 3/8", 5" WTRD TAC, P/U 31 NEW JTS 2 3/8", 2 3/8" X 2 7/8" X-O, P/U 106 NEW JTS 2 7/8", EOT @ 4,655', SECURE WELL, SDFD.
5/14/2015	6:00 7:00	1.00	PRDHEQ	28		P		CREW TRAVEL HSM WRITE & REVIEW JSA (TOPIC) LADDERS, STAIRWAYS & PLATFORMS
	7:00 12:30	5.50	PRDHEQ	24		P		CSIP 50 PSI, BLEED OFF GAS, CONTINUE PICKING UP NEW TBG W/ 206 JTS 2 7/8", TRY SET TAC @ 11,193', AFTER TWO TURNS IT TORQUED UP WON'T TURN, TRY WORK TORQUE DOWN TO TAC, IT WOULD NOT SET.

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	12:30 16:30	4.00	PRDHEQ	16		P		POOH W/ 312 JTS 2 7/8", X-O TO 2 3/8", 31 JTS 2 3/8", L/D 5" TAC, P/U 5" ARROW SET PKR W/ NO ELEMENTS ON IT, RIH W/ PKR & 31 JTS 2 3/8", X-O TO 2 7/8", RUN 112 JTS 2 7/8" TBG, EOT @ 4,851', SECURE WELL, SDFD
5/15/2015	6:00 7:00	1.00	PRDHEQ	28		P		CREW TRAVEL HSM WRITE & REVIEW JSA (TOPIC) FIRE PREVENTION
	7:00 10:30	3.50	PRDHEQ	39		P		CSIP 50 PSI, BLEED OFF GAS, CONTINUE RIH W/ 200 JTS 2 7/8", SET 5" PKR @ 11,195' IN 22K TENSION, R/D TONG & WORK FLOOR
	10:30 12:00	1.50	PRDHEQ	16		P		N/D 5K BOPS & 5K X 10K SPOOL, N/U 10 K B-FLANGE W/ 60' 3/8" CAP STRING, SECURE WELL
	12:00 13:00	1.00	RDMO	02		P		R/D NABORS RIG, CLEAN LOCATION, MOVE OFF
	13:00 15:00	2.00	PRDHEQ	18		P		WAIT FOR COROD RIG TO FINISH THE 5-17C4
	15:00 16:30	1.50	MIRU	01		P		ROAD RIG FROM 5-17C4 TO 4-13B4, MIRU COROD RIG
	16:30 18:30	2.00	PRDHEQ	18		P		RIH W/ 1,100' # 7 & 1,119' # 5, CUT COROD, POOH CUTTING UP & LAYING DOWN COROD, SECURE WELL, SDFD.
5/16/2015	6:00 7:00	1.00	PRDHEQ	28		P		CREW TRAVEL HSM WRITE & REVIEW JSA ON PICKING UP PUMP & POLISH ROD
	7:00 13:45	6.75	INARTLT	39		P		RIH W/ 2" X 1 1/2" X 38' 60 RING PA PUMP, 1369' # 6, WELD ON # 4, RUN 3619' NEW # 4, WELD ON # 5, RUN 2500' # 5, 1253' # 6, 1336' # 7, 1018' # 8, SPACE OUT COROD W/ 2-2', 6', 8' PONY SUBS, P/U POLISH ROD SEAT PUMP @ 11,323'
	13:45 14:15	0.50	INARTLT	18		P		FILL TBG W/ 15 BBLs 2% KCL, STROKE TEST PUMP TO 1000 PSI, GOOD TEST, FLUSH FLOW LINE W/ 15 BBLs
	14:15 16:00	1.75	RDMO	02		P		RIG DOWN COROD RIG, SLIDE ROTA FLEX AHEAD, HANG OFF RODS, RWTP, TWOTO, MOVE TO 4-20C4.

Table of Contents

1	General.....	1
1.1	Customer Information.....	1
1.2	Well Information.....	1
2	Summary.....	1
2.1	Operation Summary.....	1

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Ute 1420H621743			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute			
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY, L.P.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1001 Louisiana, Houston, TX, 77002		8. WELL NAME and NUMBER: Lake Fork Ranch 4-13B4			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2569 FNL 2526 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 13 Township: 02.0S Range: 04.0W Meridian: U		9. API NUMBER: 43013527190000			
PHONE NUMBER: 713 997-5138 Ext		9. FIELD and POOL or WILDCAT: ALTAMONT			
COUNTY: DUCHESNE		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/13/2016 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="text-align: center; margin-top: 20px;"> Please see attached recompletion procedure along with current and post WBD's. </div> <div style="text-align: right; margin-top: 20px;"> Accepted by the Utah Division of Oil, Gas and Mining Date: June 28, 2016 By: </div>					
NAME (PLEASE PRINT) Linda Renken		PHONE NUMBER 713 997-5138			
SIGNATURE N/A		TITLE Sr. Regulatory Analyst			
DATE 6/24/2016					

Lake Fork Ranch 4-13B4 Recom Summary Procedure

- POOH with rods, pump & tubing. Inspect/Repair/Re-furbish as needed. Replace any bad tubing and joints of rods.
- Set 15k CBP for 5" 18# casing @ 11,670'.
- Stage 1:
 - Perforate new Wasatch interval from **11,305' – 11,603'**.
 - Acid Frac Perforations with **27,000** gals 15% HCl acid (Stage 1 Recom).
- Stage 2:
 - RIH with 5" CBP & set @ 11,283'.
 - Perforate new Wasatch interval from **10,985' – 11,268'**.
 - Acid Frac Perforations **26,000** gals 15% HCl acid (Stage 2 Recom).
- Stage 3:
 - RIH w/ 5" CBP & set @ 10,858'.
 - Perforate new Upper Wasatch interval from **10,570 – 10,843'**.
 - Acid Frac perforations with **25,000** gals 15% HCl acid (Stage 3 Recom).
- Stage 4:
 - RIH w/ 7" CBP & set @ 10,005'.
 - Perforate new LGR interval from **9,738' – 9,990'**.
 - Prop Frac Perforations with **130,000** lbs 30/50 prop (w/ **6,000** lbs 100 mesh & **8,000** gals 15% HCl acid (Stage 4 Recom).
- Stage 5:
 - RIH w/ 7" CBP & set @ 9,718'.
 - Perforate new LGR interval from **9,530' – 9,703'**.
 - Acid Frac perforations with **16,000** gals 15% HCl acid (Stage 5 Recom).
- Clean out well drilling up (2) 7" CBPs and (2) 5" CBP leaving 5" 15k CBP w/15' CMT @ 11,670'. (PBSD @ 11,655') Top perf BELOW plugs @ 11,691'.
- RIH w/ production tubing and rods.
- Clean location and resume production.




Production Wellbore Schematic

Well Name: **Lake Fork Ranch 4-13B4**
 Company Name: **EP Energy**
 Field, County, State: **Altamont, Duchesne, Utah**
 Surface Location: **Lat: 40°18'27.917" N Long: 110°17'05.777" W**
 Producing Zone(s): **Wasatch**

Last Updated: **6/21/2016**
 By: **Krug**
 TD: **13,325**
 API: **43013527190000**
 AFE: **164750**

ROD DETAIL

1-1/2" x 40' Polished Rod
1192' 18/16" CoRod SE
1336' 17/16" CoRod SE
1253' 16/16" CoRod SE
2500' 15/16" CoRod SE
3650' 14/16" CoRod SE
1369' 16/16" CoRod SE
2" x 1-1/2" x 38' Insert Pump



13-3/8" 54.5# J-55 STC @ 635 ft. MD

7" TOC: 3018 ft MD

9-5/8" 40# N-80 LTC @ 5456 ft. MD

308 jts 2-7/8" 6.5 ppf L-80

7" Marker Joint at: 8662 ft MD

2-7/8" x 2 3/8" Crossover @ 10,200

Top of Liner at: 10261 ft MD

Liner TOC at: 10261 ft MD

31 jts 2-3/8" 4.7 ppf L-80

Whipstock @ 10,491' - 10,501' MD

7" 29# HCP-110 LTC @ 10606 ft. MD
Drift ID = 6.059"

Initial Completion Perf Information

Stage #6 11691 - 11934 23' /69 shots
 5000 gal HCL & 150000 lbs Power Prop 20/40
Stage #5 11963 - 12174 21' /63 shots
 5000 gal HCL & 130000 lbs Power Prop 20/40
Stage #4 12204 - 12441 22' /66 shots
 5000 gal HCL & 130030 lbs Power Prop 20/40
Stage #3 12481 - 12683 20' /60 shots
 5000 gal HCL & 130010 lbs Power Prop 20/40
Stage #2 12713 - 12980 23' /69 shots
 5000 gal HCL & 133100 lbs Power Prop 20/40
Stage #1 13010 - 13252 22' /66 shots
 5000 gal HCL & 130000 lbs Power Prop 20/40

5" Arrow Set Pkr @ 11,189'
(elements removed)
4 jts 2-3/8" 4.7# L-80 tubing
Seating Nipple @ 11,323'
4' x 2 3/8" Tubing Sub
31' X 2-3/8" #5 Desander
2 jt 2-3/8" 4.7# L-80
EOT @ 11,424'


5" 18# HCP-110 STL @ 10261 - 13369 ft. MD
Drift ID = 4.151"



Proposed Recom Wellbore Schematic

Well Name: **Lake Fork Ranch 4-13B4**
 Company Name: **EP Energy**
 Field, County, State: **Altamont, Duchesne, Utah**
 Surface Location: **Lat: 40°18'27.917" N Long: 110°17'05.777" W**
 Producing Zone(s): **Wasatch**

Last Updated: **6/21/2016**
 By: **Krug**
 TD: **13,325**
 API: **43013527190000**
 AFE: **164750**



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

RECOMPLETION

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG										5. LEASE DESIGNATION AND SERIAL NUMBER:																			
										6. IF INDIAN, ALLOTTEE OR TRIBE NAME																			
1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____										7. UNIT or CA AGREEMENT NAME																			
b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____										8. WELL NAME and NUMBER:																			
2. NAME OF OPERATOR:										9. API NUMBER:																			
3. ADDRESS OF OPERATOR: CITY _____ STATE _____ ZIP _____										PHONE NUMBER: _____																			
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:										10 FIELD AND POOL, OR WILDCAT																			
										11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: U.S.B. & M.																			
										12. COUNTY					13. STATE UTAH														
14. DATE SPUDDED:			15. DATE T.D. REACHED:			16. DATE COMPLETED: ABANDONED <input type="checkbox"/> READY TO PRODUCE <input type="checkbox"/>				17. ELEVATIONS (DF, RKB, RT, GL):																			
18. TOTAL DEPTH: MD _____ TVD _____			19. PLUG BACK T.D.: MD _____ TVD _____			20. IF MULTIPLE COMPLETIONS, HOW MANY? *				21. DEPTH BRIDGE MD _____ PLUG SET: TVD _____																			
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)										23. WAS WELL CORED? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit copy)																			
24. CASING AND LINER RECORD (Report all strings set in well)																													
HOLE SIZE		SIZE/GRADE		WEIGHT (#/ft.)		TOP (MD)		BOTTOM (MD)		STAGE CEMENTER DEPTH		CEMENT TYPE & NO. OF SACKS		SLURRY VOLUME (BBL)		CEMENT TOP **		AMOUNT PULLED											
25. TUBING RECORD																													
SIZE		DEPTH SET (MD)		PACKER SET (MD)		SIZE		DEPTH SET (MD)		PACKER SET (MD)		SIZE		DEPTH SET (MD)		PACKER SET (MD)													
26. PRODUCING INTERVALS										27. PERFORATION RECORD																			
FORMATION NAME		TOP (MD)		BOTTOM (MD)		TOP (TVD)		BOTTOM (TVD)		INTERVAL (Top/Bot - MD)		SIZE		NO. HOLES		PERFORATION STATUS													
(A)																Open <input type="checkbox"/> Squeezed <input type="checkbox"/>													
(B)																Open <input type="checkbox"/> Squeezed <input type="checkbox"/>													
(C)																Open <input type="checkbox"/> Squeezed <input type="checkbox"/>													
(D)																Open <input type="checkbox"/> Squeezed <input type="checkbox"/>													
28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.																													
DEPTH INTERVAL					AMOUNT AND TYPE OF MATERIAL																								
29. ENCLOSED ATTACHMENTS:															30. WELL STATUS:														
<input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS															<input type="checkbox"/> GEOLOGIC REPORT					<input type="checkbox"/> DST REPORT					<input type="checkbox"/> DIRECTIONAL SURVEY				
<input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION															<input type="checkbox"/> CORE ANALYSIS					<input type="checkbox"/> OTHER: _____									

31. INITIAL PRODUCTION**INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)**33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) _____ TITLE _____

SIGNATURE _____ DATE _____

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Attachment to Well Completion Report

Form 8 Dated: _

Well Name: _

Items #27 and #28 Continued

27. Perforation Record

Interval (Top/Bottom-MD)	Hole Size	No. of Holes	Perf. Status

28. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material

CENTRAL DIVISION

ALTAMONT FIELD
LAKE FORK RANCH 4-13B4
LAKE FORK RANCH 4-13B4
RECOMPLETE LAND

Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

1 General

1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

1.2 Well Information

Well	LAKE FORK RANCH 4-13B4		
Project	ALTAMONT FIELD	Site	LAKE FORK RANCH 4-13B4
Rig Name/No.		Event	RECOMPLETE LAND
Start date	7/27/2016	End date	9/24/2016
Spud Date/Time	7/3/2014	UWI	LAKE FORK RANCH 4-13B4
Active datum	KB @6,082.7usft (above Mean Sea Level)		
Afe No./Description	166959/57007 / LAKE FORK RANCH 4-13B4		

2 Summary

2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
7/29/2016	6:00 7:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON ROADING RIG & EQUIP TO LOC, WRITE & REVIEW JSA'S
	7:00 8:00	1.00	MIRU	01		P		ROAD COROD RIG TO LOC, SLIDE P.U. BACK SPOT IN & RU RIG
	8:00 13:00	5.00	PRDHEQ	03		P		LD POLISH ROD, ATTEMPT TO UNSEAT PMP FAILED, J-OFF ON-OFF TOOL, POOH W/ 1118' #8, 1336' #7, 1253' #6, 2500' #5, 3650' #4, 1369' #6 COROD & ON-OFF TOOL, RD COROD RIG & MOVE OFF LOC
	13:00 14:00	1.00	MIRU	01		P		MIRU PEAK 1500
	14:00 16:00	2.00	PRDHEQ	21		P		MIRU W.L. RIH & PERF 2-3/8" TBG @ 11255', VERY WAXY GETTING W.L. IN HOLE
	16:00 19:00	3.00	PRDHEQ	16		P		NDWH, BREAK OUT & LD 10K B-FLANGE, MU 6' 2-7/8" PERF SUB, TBG HANGER W/ 2 WAY CHECK, TAC NOT SET, LAND TBG ON HANGER, NU 10K SPOOL, 10K X 5K SPOOL & BOP, TEST FLANGE CONNECTIONS, PIPE RAMS & BLIND RAMS, GOOD TEST, SECURE WELL, WELL BORE HOLDING FLUID BARRIER 1, PIPE RAMS SHUT & LOCKED BARRIER 2, CSG VALVES SHUT & NIGHT CAPPED BARRIER 1 & 2, CLOSE & NIGHT CAP TIW VALVE BARRIER 1 & 2, SDFN
7/30/2016	6:00 7:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON SCANNING TBG OUT OF HOLE, WRITE & REVIEW JSA'S
	7:00 14:00	7.00	PRDHEQ	39		P		0 PSI ON WELL, RU TBG SCANNERS, SCAN OUT OF HOLE W/ 311 JTS 2-7/8" EUE L-80 TBG, 278 JTS Y.B. & 33 JTS BLUE BAND, 37 JTS 2-3/8" EUE N-80 TBG, 21 JTS Y.B., 14 JTS B.B. & 2 JTS R.B., LD PROD BHA, RDMP TBG SCANNERS
	14:00 19:00	5.00	WLWORK	26		P		RU W.L. LUBE TEST BOP & LUBE TO 4800 PSI GOOD TEST, RUN 6" GR/JD TO 5" LT @ 10261', RUN 4-1/8" GR/JB TO 11670', RIH SET 5" MAGNUM 15K PLUG @ 11660' (CSG COLLAR @ 11652') DUMP BAIL 15' CMT ON TOP OF PLUG, RD W.L. SECURE WELL, 5" CBP BARRIER 1, BLIND RAMS SHUT & LOCKED BARRIER 2, CLOSE & NIGHT CAP CSG VALVES BARRIER 1 & 2, SDFW
7/31/2016	6:00 6:00	24.00	WOR	18		P		NO ACTIVITY SDFW
8/1/2016	6:00 6:00	24.00	WOR	28		P		NO ACTIVITY SDFW
8/2/2016	7:00 8:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON RIH W/ TBG WRITE & REVIEW JSA'S

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	8:00 11:00	3.00	PRDHEQ	39		P		0 PSI ON WELL, MU & RIH W/ 2-3/8" BULL PLUG, 4' X 2-3/8" PERF SUB, 2-3/8" P.S.N., 20 JTS 2-3/8" EUE L-80, 2-7/8" X 2-3/8" EUE X OVER & 278 JTS 2-7/8" EUE L-80 TBG, MU TBG HANGER W/ B.P.V. & LAND TBG ON HANGER, EOT @ 9706'
	11:00 14:30	3.50	PRDHEQ	16		P		RD WORK FLOOR, NDBOP, NU 10K MASTER VALVE, PULL BACK PRESSURE VALVE OUT, INSTALL 2 WAY CHECK, PRESSURE TEST MASTER VALVE CONNECTION TO 8500 PSI, PULL OUT 2 WAY CHECK, TEST CSG TO 8000 PSI FOR 30 MIN GOOD TEST, NU 10K NIGHT CAP
	14:30 17:00	2.50	RDMO	02		P		SECURE WELL, 5" PLUG BARRIER 1, 10K MASTER VALVE BARRIER 2, SHUT & NIGHT CAP CSG VALVES BARRIER 1 & 2, RIG DWN RIG, ROAD RIG TO 2-28C4 SPOT IN & RU, SDFN
8/17/2016	6:00 7:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON NU & TESTING BOP WRITE & REVIEW JSA'S
	7:00 8:30	1.50	WOR	16		P		0 PSI ON WELL, NDWH, NU & TEST BOP, RU WORK FLOOR & TBG TONGS
	8:30 11:30	3.00	PRDHEQ	39		P		POOH LD TBG HANGER, TOO H & STAND BACK IN DERRICK W/ 278 JTS 2-7/8" TBG, 2-7/8" X 2-3/8" EUE XOVER. 20 JTS 2-3/8" TBG, 2-3/8" P.S.N., 4' X 2-3/8" PERF SUB & 2-3/8" BULL PLUG
	11:30 14:00	2.50	PRDHEQ	16		P		NDBOP, NU FRAC STACK TEST STACK TO 9500 PSI GOOD TEST, RUN FLOW BACK LINES & TEST TO 8000 PSI GOOD TEST SECURE WELL, BARRIER 1 5" PLUG, BARRIER 2 CLOSE FRAC VALVE, HCR VALVES SHUT & LOCKED, CLOSE & NIGHT CAP CSG VALVES SDFN
8/18/2016	6:00 7:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON WORKING W/ WIRE LINE WRITE & REVIEW JSA'S
	7:00 10:00	3.00	WLWORK	18		P		MIRU THE PERFORATORS W.L. & TEST LUBE & EQUIP
	10:00 14:00	4.00	WLWORK	21		P		RIH W/ 2-3/4" PERF GUNS PERF STG 1 PERFS FROM 11598' TO 11304', USING TAG RTG GUNS 16 GRAM CHARGES, 3 SPF @ 120 DEG PHASING, ALL PERFS CORRELATED TO CUTTERS CBL LOG DATED 8/18/14, STARTING PRESSURE 1000 PSI, ENDING PRESSURE 0 PSI WELL ON VACUME, POOH SECURE WELL, CLOSE FRAC VALVE BARRIER 1, CLOSE HCR VALVES & LOCK BARRIER 2, CLOSE & NIGHT CAP CSG VALVES SDFN
8/19/2016	6:00 7:00	1.00	STG01	28		P		CT HOLD SAFETY MTG ON ACIDIZING & W.L. OPERATIONS, WRITE & REVIEW JSA'S
	7:00 8:00	1.00	STG01	35		P		PRESSURE TEST PUMP LINES TO 9272 PSI. OPEN WELL. SICP 0 PSI. FILL CSG W/ 232 BBLS WTR, BREAK DOWN STAGE 1 PERFORATIONS @ 4553 PSI, PUMPED TOTAL OF 306 BBLS, PERFORM STEP RATE SHUT DWN, ISIP 3406 PSI, F.G. .73, 0 PSI IN 4 MIN, TREAT STG 1 PERFS W/ 27,000 GALLONS 15% HCL ACID DROPPING 84 BIO BALLS THRU OUT ACID, FLUSH 10 BBLS PAST BTM PERF ISIP 3384 PSI. FG .83. 5 MIN 3073 PSI. 10 MIN 1957 PSI. AVG RATE 50.3 BPM. MAX RATE 54.6 BPM. AVG PSI 6308 PSI. MAX PSI 6564 PSI. 1365 BBLS WATER TO RECOVER SHUT IN BTM HCR VALVE & TURN WELL OVER TO W.L.
	8:00 10:00	2.00	STG02	21		P		TEST LUBRICATOR TO 4000 PSI, RIH & SET 5" CBP @ 11276'. PERFORATE STAGE 2 PERFORATIONS FROM 11261' TO 10987', USING 2-3/4" TAG-RTG GUNS, 16 GRAM CHARGES, 3 SPF, 120 DEGREE PHASING. ALL PERFS CORRELATED TO THE CUTTERS W.L. CBL/GR/CCL RUN 1 LOG DATED 8/18/14, STARTING PRESSURE 0 PSI, ENDING 0 PSI, POOH W/ W.L., SHUT WELL IN W/ BTM HCR VALVE & TURN OVER TO FRAC CREW.

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	10:00 11:15	1.25	STG02	35		P		PRESSURE TEST PUMP LINES TO 9350 PSI. OPEN WELL. SICP 0 PSI. FILL CSG W/ 158 BBLS WTR, BREAK DOWN STAGE 2 PERFORATIONS @ 4020 PSI, PUMPED TOTAL OF 256 BBLS, PERFORM STEP RATE SHUT DWN, ISIP 3368 PSI, F.G. .74, 0 PSI IN 3 MIN, TREAT STG 2 PERFS W/ 26,000 GALLONS 15% HCL ACID DROPPING 84 BIO BALLS THRU OUT ACID, FLUSH 10 BBLS PAST BTM PERF ISIP 4135 PSI. FG .80. 5 MIN 2018 PSI. 10 MIN 736 PSI. AVG RATE 45.9 BPM. MAX RATE 50.3 BPM. AVG PSI 5138 PSI. MAX PSI 5710 PSI. 1284 BBLS WATER TO RECOVER SHUT IN BTM HCR VALVE & TURN WELL OVER TO W.L.
	11:15 12:45	1.50	STG03	21		P		TEST LUBRICATOR TO 4000 PSI, RIH & SET 5" CBP @ 10864'. PERFORATE STAGE 3 PERFORATIONS FROM 10838' TO 10635' USING 2-3/4" TAG-RTG GUNS, 16 GRAM CHARGES, 3 SPF, 120 DEGREE PHASING. ALL PERFS CORRELATED TO THE CUTTERS W.L. CBL/GR/CCL RUN 1 LOG DATED 8/18/14, STARTING PRESSURE 0 PSI, ENDING 0 PSI, POOH W/ W.L., SHUT WELL IN W/ BTM HCR VALVE & TURN OVER TO FRAC CREW.
	12:45 14:00	1.25	STG03	35		P		PRESSURE TEST PUMP LINES TO 9160 PSI. OPEN WELL. SICP 0 PSI. FILL CSG W/ 116 BBLS WTR, BREAK DOWN STAGE 3 PERFORATIONS @ 4005 PSI, PUMPED TOTAL OF 202 BBLS, PERFORM STEP RATE SHUT DWN, ISIP 2935 PSI, F.G. .71, 5 MIN 646 PSI, 10 MIN 219 PSI 0 PSI IN 7 MIN, TREAT STG 3 PERFS W/ 20,000 GALLONS 15% HCL ACID DROPPING 84 BIO BALLS THRU OUT ACID, FLUSH 10 BBLS PAST BTM PERF ISIP 2935 PSI. FG .80. 5 MIN 2443 PSI. 10 MIN 979 PSI. AVG RATE 49.5 BPM. MAX RATE 49.9 BPM. AVG PSI 4467 PSI. MAX PSI 7477 PSI. 1017 BBLS WATER TO RECOVER SHUT IN BTM HCR VALVE & TURN WELL OVER TO W.L.
	14:00 16:30	2.50	STG04	21		P		TEST LUBRICATOR TO 4000 PSI, RIH & SET 7" CBP @ 10005'. PERFORATE STAGE 4 PERFORATIONS FROM 9984' TO 9734', USING 3-1/8" TAG-RTG GUNS, 22.7 GRAM CHARGES, 3 SPF, 120 DEGREE PHASING. ALL PERFS CORRELATED TO THE CUTTERS W.L. CBL/GR/CCL RUN 1 LOG DATED 8/18/14, STARTING PRESSURE 0 PSI, ENDING 0 PSI, POOH W/ W.L., SECURE WELL SHUT MASTER VALVE BARRIER 1, SHUT & LOCK HCR VALVES BARRIER 2, CLOSE & NIGHT CAP CSG VALVES BARRIER 1 & 2, GREASE & RE TORQUE FRAC STACK, SDFN
8/20/2016	6:00 7:00	1.00	STG04	28		P		CT HOLD SAFETY MTG ON WORKING W/ FRAC & ACID OPERATIONS, WRITE & REVIEW JSA'S
	7:00 10:00	3.00	STG04	18		P		OFF LOAD & MIX ACID
	10:00 12:00	2.00	STG04	35		P		PRESSURE TEST PUMP LINES TO 9337 PSI. OPEN WELL. SICP 1105 PSI. BREAK DOWN STAGE 4 PERFORATIONS @ 4061 PSI, PUMPING 8.2 BPM, TREAT STG 4 PERFS W/ 8000 GALLONS 15% HCL ACID, PERFORM STEP RATE SHUT DOWN TEST. ISIP 3239 PSI. FG .76. 5 MIN 2699 PSI. 10 MIN 2404 PSI. 15 MIN 2209 PSI. TREAT STAGE 4 PERFORATIONS W/ 6030 LBS 100 MESH SAND IN 1/2 PPG STAGE & 125,000 LBS WHITE 30/50 SAND IN 1/2 PPG, 1 PPG, 1.5 PPG, 2 PPG & 3 PPG STAGES. ISIP 3992 PSI. FG .84. AVG RATE 73.3 BPM. MAX RATE 75.1 BPM. AVG PSI 5258 PSI. MAX PSI 6161 PSI. 4127 BBLS WATER TO RECOVER SHUT IN BTM HCR VALVE & TURN WELL OVER TO W.L.

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	12:00 14:15	2.25	STG05	21		P		TEST LUBRICATOR TO 4000 PSI, RIH & SET 7" CBP @ 9712'. PERFORATE STAGE 5 PERFORATIONS FROM 9694' TO 9522', USING 3-1/8" TAG-RTG GUNS, 22.7 GRAM CHARGES, 3 SPF, 120 DEGREE PHASING. ALL PERFS CORRELATED TO THE CUTTERS W.L. CBL/GR/CCL RUN 1 LOG DATED 8/18/14, STARTING PRESSURE 2700 PSI, ENDING 2400 PSI, POOH W/ W.L., SHUT WELL IN W/ BTM HCR VALVE & TURN OVER TO FRAC CREW.
	14:15 15:00	0.75	STG05	35		P		PRESSURE TEST PUMP LINES TO 9291 PSI. OPEN WELL. SICP 1884 PSI. BREAK DOWN STAGE 5 PERFORATIONS @ 5036 PSI, PUMPED TOTAL OF 67 BBLS, PERFORM STEP RATE SHUT DWN, ISIP 3339 PSI, F.G. .78, 5 MIN 3011 PSI, 10 MIN 2874 PSI, 15 MIN 2782 PSI, TREAT STG 5 PERFS W/ 17,000 GALLONS 15% HCL ACID DROPPING 80 BIO BALLS THRU OUT ACID, FLUSH 10 BBLS PAST BTM PERF ISIP 3257 PSI. FG .77. 5 MIN 2895 PSI. 10 MIN 2772 PSI. AVG RATE 43.1 BPM. MAX RATE 51.1 BPM. AVG PSI 4236 PSI. MAX PSI 6986 PSI. 836 BBLS WATER TO RECOVER SHUT IN MASTER FRAC VALVE BARRIER 1, SHUT & LOCK HCR VALVES BARRIER 2, CLOSE & NIGHT CAP CSG VALVES BARRIER 1 & 2
	15:00 18:00	3.00	RDMO	02		P		RIG DWN & MOVE OUT W.L. & FRAC EQUIP
	18:00 6:00	12.00	FB	19		P		TURN WELL OVER TO FLOW BACK CREW, OPEN WELL TO FLOW BACK TANK, 2300 PSI ON 12/64 CHOKE, CURRENT PRESSURE 1950 PSI ON 12/64 CHOKE FLOWED BACK 558 BBLS WTR
8/21/2016	6:00 6:00	24.00	FB	19		P		HOLD AFETY MTG ON CHANGING CHOKES WRITE & REVIEW JSA'S, CURRENT CSG PRESSURE 1300 PSI FLOWING ON 18/64 CHOKE FLOWED 161 BBLS OIL, 1079 BBLS WTR, GAS FLARING
8/22/2016	6:00 6:00	24.00	FB	19		P		HOLD SAFETY MTG ON GAUGING TANKS WRITE & REVIEW JSA'S, WELL FLOWING CURRENT PSI 1000 PSI, ON 18/64 CHOKE, FLOWED 502 BBLS OIL, 662 BBLS WTR
8/23/2016	6:00 6:00	24.00	FB	19		P		HOLD SFETY MTG ON PROPPER PPE, WRITE & REVIEW JSA'S, CURRENT WELL PRESSURE 750 PSI, ON 18/64 CHOKE, FLOWED 586 BBLS OIL & 360 BBLS WTR, GAS FLARING
8/24/2016	6:00 7:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON ND FRAC STACK WRITE & REVIEW JSA'S
	7:00 8:00	1.00	WOR	16		P		ND FRAC STACK TO LOWER 7" HCR VALVE
	8:00 12:30	4.50	WLWORK	20		P		RU THE PERFORATORS W.L., TEST LUBRICATOR, RIH W/ 6" GR/JB TO 9500', POOH, MU & RIH W/ 7" ASX-1 PKR W/ PUMP OUT PLUG & PLUG CATCHER, RIH & SET C.E. OF PKR @ 9480', POOH & RD W.L.
	12:30 14:00	1.50	FB	19		P		BLOW WELL DWN TO PROD FACILITY, TURN WELL TO FLOW BACK TANK & PERFORM NEGATIVE TEST, NO FLOW
	14:00 15:15	1.25	WOR	16		P		ND LOWER HCR VALVE, BARRIER 1 PKR BARRIER 2 10K MANUAL FRAC VALVE CLOSED, NU & TEST BOP, RU WORK FLOOR & TBG TONGS
	15:15 16:00	0.75	PRDHEQ	39		P		RIH OUT OF DERRICK W/ 20 JTS 2-3/8" EUE L-80 TBG, POOH & LD 2-3/8" TBG
	16:00 16:00	0.00	POST	39		P		MU & RIH W/ 7" 10K ON-OFF TOOL, TALLY & TIH OUT OF DERRICK W/ 278 JTS 2-7/8" EUE L-80 Y.B. TBG, EOT @ 9071' SECURE WELL, PKR W/ PUMP OUT PLUG BARRIER 1, SHUT & LOCK PIPE RAMS BARRIER 2, CLOSE & NIGHT CAP CSG VALVES BARRIER 1 & 2, CLOSE & NIGHT CAP TIW VALVE BARRIER 1 & 2, SDFN
8/25/2016	6:00 7:00	1.00	WOR	28		P		CT HOLD SAFETY MTG ON PU TBG OFF TRAILER WRITE & REVIEW JSA'S
	7:00 8:30	1.50	PRDHEQ	24		P		SICP & SITP 200 PSI BLOW DWN WELL TO FLOW BACK TANK, PU & RIH W/ 13 JTS 2-7/8" TBG & LATCH ONTO PKR & PULL 15K OVER STRING WT, J-OFF PKR LD 1 JT 2-7/8" TBG

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	8:30 11:00	2.50	PRDHEQ	06		P		CIRC 360 BBLs 2% KCL MIXED W/ PKR FLUID DWN TBG UP CSG TO FLOW BACK TANK
	11:00 13:30	2.50	PRDHEQ	13		P		POOH W/ 1 JT 2-7/8" TBG, MU & RIH W/ 8', 6' & 4' X 2-7/8" EUE N-80 TBG SUBS & 1 JT 2-7/8" TBG, MU TBG HANGER W/ B.P.V. LAND TBG ON HANGER, RUN DOGS IN ON HANGER, J-OUT OF HANGER, RUN IN LATCH ONTO PKR, PULL UP 12K & J BACK INTO HANGER & LAND TBG, TEST CSG TO 1000 PSI GOOD TEST, RD WORK FLOOR, NDBOP & MASTER FRAC VALVE, NU FLOW TREE & FLOW LINES, PULL B.P.V. & REPLACE W/ 2 WAY CHECK, TEST WELL HEAD GOOD TEST, PULL 2 WAY CHECK, RD RIG, PUMP OUT PLUG @ 2700 PSI, TWOTFBC 600 PSI ON 18/64 CHOKE, PU LOCATION & MOVE OUT
9/17/2016	6:00 7:00	1.00	PRDHEQ	16		P		TRAVEL TO LOC HSM, REVIEW JSA WELL CONTROL AND NU
	7:00 12:00	5.00	PRDHEQ	16		P		SIWP= 0 PSI CSG, 100 PSI TUBING, CONTROL WELL W/ 60 BBLs KCL DOWN TUBING INSTAL BPV ND W/H NU AND TEST BOPS AND HYD, GET OFF ON OFF TOOL REMOVE BREECH LOCK HNGR RIH GET BACK ON PKR RELEASE PKR.
	12:00 19:30	7.50	PRDHEQ	39		P		POOH W/ PKR TUBING PLUGGED W/ OIL CIRC HOT WTR DOWN CSG FLUSH TUB VOL CUNTINUE TO POOH TUBING PLUGGED AGAIN SD CIRC DOW TUB UP CSG CLEAN W/ 205 BBL HOT KCL, SHUT AND LOCK PIPE RAMS CLOSE CSG VALVES W/ BULL PLUG CLOSE TIW W/ NIGHT CAP SDFN
9/18/2016	6:00 7:00	1.00	PRDHEQ	39		P		TRAVEL TO LOC HSM, REVIEW JSA= WELL CONTROL, TRIPING TUBING, HOT OILER
	7:00 9:30	2.50	PRDHEQ	39		P		SIWP= 0 PSI OPEN WELL CONTINUE TO POOH W/ HOT WTR TRICKLING DOWN ANN.LD BHA
	9:30 12:00	2.50	PRDHEQ	39		P		PU 6" ROCK BIT RIH TALLEY AND PU 7 JNTS TAG 1ST CBP @9709'
	12:00 15:00	3.00	WOR	18		P		RU PWR SWVL TROUBLE CIRC DUE TO OIL PLUGS CLEAR TUBING RU HOT OILER AND PUMP HOT WTR AND RIG PUMP EST GOOD REV CIRC DRILL THRU CBP IN 30 MIN W/100 PSI INCREASE IN PRESS WELL FLOWING
	15:00 19:00	4.00	WOR	18		P		CONTINUE TO RIH TAG @ 10011' EST REV CIRC PWR SWVL TORQ OUT AND STOP ROTATING UNLESS TUBING WAS MOVING DRILLING SLOW CANT KEEP WEIGHT ON BIT WITHOUT TORQUING OUT DRILL 1-1/2 HOURS MADE 15' TO 10216' TAGGED SOLID COLLAR AT DRILLING HEAD CIRC CLEAN SHUT DOWN PUMP WELL FLOWED 1 HOUR 1-1/2 BPM NOT SLOWING DOWN POOH W/ 20 JNTS TO GET ABOVE PERFS SHUT AND LOCK PIPE RAMS, CLOSE HYDRILL, CLOSE CSG VALVES, CLOSE TIW W/ NIGHT CAP SDFN
9/19/2016	6:00 7:00	1.00	WOR	18		P		TRAVEL TO LOC HSM, REVIEW JSA , DRILLING AND PUMPING
	7:00 9:00	2.00	WOR	18		P		SIWP= OPEN CSG TO FBT, ND PWR SWVL PU NEW PWR SWVLOPEN CSG TO FBT PUMP 15 BBL BRINE DWN TUB TO CONTROL WELL RIH TAG CBP @ 10026 EST REV CIRC (SWVL BETTER) DRILL THRU 2ND CBP IN 35 MIN W/ LOSS OF RETURNS CIRC CLEAN
	9:00 12:00	3.00	WOR	18		P		CONTINUE TO RIH TAG L/T @ 10257'EST REV CIRC CLEAN UP REMAINING PLUG CIRC CLEAN CONTROL TUB W/ 15 BBL BRINE HANG BACK PWR SWVL
	12:00 15:00	3.00	WOR	39		P		POOH W/ 6" BIT AT 3000' LEFT ROLL HOLE W/ BRINE 60 BBL CONTINUE TOPPH LD BIT
	15:00 18:00	3.00	WOR	39		P		P.U. 4-1/8" BIT ANB BIT SUB TALLEY & PU 47 JNTS 2-3/8" X-OVER 242 JNTS 2-7/8" EOT @ 9400' CLOSE AND LOCK PIPE RAMS CLOSE HYDRILL CLOSE CSG VALVES W/ BULL PLUG CLOSE TIW W/ NIGHT CAP SDFN
9/20/2016	7:00 8:00	1.00	WOR	18		P		TRAVEL TO LOC HSM, REVIEW JSA =DRILLING & CIRCULATING

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	8:00 9:00	1.00	WOR	18		P		SIWP= 0 PSIRIH TAG L/T RU PWR SWVL EST CIRC C/O AND DRILL FELL INTO LINER W/ BIT
	9:00 15:00	6.00	WOR	18		P		CONTINUE TO RIH TAG AT 10830EST REV CIRC C/O AND DRILL TO CBP AT 10853' PART WAY THRU PLUG LOST CIRC WORK TUBING SURGE MANIFOLD SEVERAL TIMES WORK TUBING SWITCH TO CONV CIRC GOOD RETURNS DRILL THRU CBP CIRC 30 MIN
	15:00 19:00	4.00	WOR	18		P		CONTINUE TO RIH TAG 11250'EST CONV CIRC C/O TO CBP @ 11276' DRILL SLOWLY ON PLUG PART WAY THRU LOST ALL CIRC MIX AND PUMP POLY SWEEP CONTINUE TO PUMP DOWN TUB UP CSG 90 MIN NO RETURNS POOH ABOVE L/T EOT @ 10100' CLOSE AND LOCK PIPE RAMS CLOSE HYD. CLOSE CSG VALVE, W/ BULL PLUG CLOSE TIW W/ NIGHT CAP SDFN, TOTAL FLUID LOST TODAY 850 BBLs, FLUID LOST AFTER LOST CIRC 280 BBLs
9/21/2016	6:00 7:00	1.00	WOR	18		P		TRAVEL TO LOC HSM REVIEW JSA= PUMP W/ 2 PUMPS HANDLING POLY
	6:00 7:00	1.00	WOR	18		P		TRAVEL TO LOC HSM REVIEW JSA= PUMP W/ 2 PUMPS HANDLING POLY
	7:00 10:00	3.00	WOR	18		P		SIWP=0 PSI, RIH TAG @ 11590' MI RU 2ND PUMP EST REV CIRC @ 300 BBLs C/O AND DRILL THRU CBP @ 11275' CIRC CLEAN
	7:00 10:00	3.00	WOR	18		P		SIWP=0 PSI, RIH TAG @ 11590' MI RU 2ND PUMP EST REV CIRC @ 300 BBLs C/O AND DRILL THRU CBP @ 11275' CIRC CLEAN
	10:00 13:00	3.00	WOR	18		P		CONTINUE TO RIH TAG @ 11570' EST CIRC C/O & DRILL 11630 CIRC CLEAN LOST 1700 BBL PULL OUT OF LINER FLUSH OIL OUT OF TUBING
	10:00 13:00	3.00	WOR	18		P		CONTINUE TO RIH TAG @ 11570' EST CIRC C/O & DRILL 11630 CIRC CLEAN LOST 1700 BBL PULL OUT OF LINER FLUSH OIL OUT OF TUBING
	13:00 16:00	3.00	WOR	18		P		CONTINUE TO POOH LD 2-3/8" TUBING AND BIT (STOPED SEVERAL TIMES TO FLUSH OIL OUT OF TUBING
	13:00 16:00	3.00	WOR	18		P		CONTINUE TO POOH LD 2-3/8" TUBING AND BIT (STOPED SEVERAL TIMES TO FLUSH OIL OUT OF TUBING
	16:00 19:00	3.00	WOR	18		P		MIRU HYDRO TEST UNIT PU BHA SIH W/ PROD TESTING TO 8500 PSI EOT @ 1400' CLOSE AND LOCK PIPE RAMS, CLOSE HYDRILL, CLOSE CSG VALVES W/ BULL PLUG, CLOSE TIW W/ NIGHT CAP SDFN
	16:00 19:00	3.00	WOR	18		P		MIRU HYDRO TEST UNIT PU BHA SIH W/ PROD TESTING TO 8500 PSI EOT @ 1400' CLOSE AND LOCK PIPE RAMS, CLOSE HYDRILL, CLOSE CSG VALVES W/ BULL PLUG, CLOSE TIW W/ NIGHT CAP SDFN
9/23/2016	6:00 7:00	1.00	INSTUB	39		P		TRAVEL TO LOC HSM, JSA= HYDRO TESTING TUBING, NU HOT OILING
	7:00 12:00	5.00	INSTUB	39		P		SIWP=200 PSI, CONTINUE TO RIH HYDRO TEST PROD TUBING ALL JNTS GOOD
	12:00 14:00	2.00	WOR	18		P		RD HYDRO TESTER SET TAC @ 10010.37' SN@ 10113.48' W/ 23000# TENSION LAND TUB ON HNGR RD FLOOR AND TUBING EQUIP ND BOPS AND HYDRILL NU B FLANGE NU WELL HEAD RD RIG MO (MOVE RIG TO ESPLEY 1-15C4)
	14:00 19:00	5.00	INARTLT	03		P		MIRU CO-ROD RIG FLUSH TUBING W/ 60 BBL OF INHIBITED KCL PU 2-1/2" X 1-3/4" X 38' INSERT PUMP RIH W/ 16 & 14 COROD POOH CUT AND LD 14 COROD SIW SDFN
9/24/2016	6:00 7:00	1.00	INARTLT	03		P		TRAVEL TO LOC HSM JSA= RUNING COROD, HOT OILING
	6:00 7:00	1.00	INARTLT	03		P		TRAVEL TO LOC HSM JSA= RUNING COROD, HOT OILING
	7:00 9:00	2.00	INARTLT	03		P		SPLICE AND WELD 500' 16/16
	7:00 9:00	2.00	INARTLT	03		P		SPLICE AND WELD 500' 16/16
	9:00 12:00	3.00	INARTLT	03		P		SPLICE AND WELD AND RUN 2000' 15/16'
	9:00 12:00	3.00	INARTLT	03		P		SPLICE AND WELD AND RUN 2000' 15/16'

2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activit y Code	Sub	OP Code	MD from (usft)	Operation
	12:00 15:00	3.00	INARTLT	03		P		RUN REMAINING CO ROD TAG SPACE OUT SPLICE AND WELD SEAT PUMP NU WELLHEAD PRESS TEST PUMP TO 1000 PSI RD CO-ROD RIG SLIDE UNIT HANG OFF RODS ON UNIT TURN WELL OVER TO PRODUCTION
	12:00 15:00	3.00	INARTLT	03		P		RUN REMAINING CO ROD TAG SPACE OUT SPLICE AND WELD SEAT PUMP NU WELLHEAD PRESS TEST PUMP TO 1000 PSI RD CO-ROD RIG SLIDE UNIT HANG OFF RODS ON UNIT TURN WELL OVER TO PRODUCTION